

Construction Notes:

- 12'x12' dumpster pad w/ 10' apron w/ 6' tall brick enclosure. Dimensions shall be measured from face of bollards.
- All fill subgrade and base material shall be in accordance with geotechnical report 'Report of Subsurface Exploration and Geotechnical Study Proposed Crawford Electric Supply Building West of North Earl Rudder Freeway (State Highway 6) and Osborn Lane Bryan, Brazos County, Texas' Prepared by CME Testing and Engineering, Inc on June 23, 2015.
- All concrete to be constructed with 4,000 psi (Min) - 28 day strength portland cement concrete.
- All items to be removed during clearing and grubbing. Remove not only the above ground elements, but all underground elements as well. All excavated material shall become the property of the contractor unless otherwise directed by the Owner. All debris must be disposed of off site.
- Prior to grading operations, contractor is to strip the first 6" of soil. Contractor shall proof roll the entire site and remove any unstable materials according to TxDOT Specifications. Select fill is to be used in replacing objectionable material.
- Assure positive drainage across project site to the storm water structures.
- Normal Domestic Wastewater is anticipated to be discharged from this development.
- Potable Water Protection - All devices, appurtenances, appliances, and apparatus intended to serve some special function and that connects to the water supply system, shall be provided with protection against backflow and contamination of the water supply system.
- Irrigation System - Potable water supply must be protected by either an atmospheric or pressure vacuum breaker, or testable double check valve assembly, and installed per City Ordinance.
- Each utility contractor is responsible for positioning and trenching of service lines. Mark all lines with utility tape. Utility contractors are responsible for coordinating with paving contractor in placement and installation of any necessary utility conduit prior to subgrade preparation. Lines requiring slope control are to be installed first. All other lines not requiring slope control or elevation shall be installed deepest first. Each contractor is responsible for knowing final determination of installation order.
- Materials and methods for pavement markings shall conform to TxDOT Standard Specifications for Construction of Highways, Streets, and Bridges (current edition), with the following exceptions: 1) Type II marking materials need not be purchased from the Department, and 2) Glass beads may be omitted, but marking material shall be Type II paint-type material.
- The Contractor shall be responsible for the containment and proper disposal of all liquid and solid waste associated with this project. The Contractor shall use all means necessary to prevent the occurrence of windblown letter from the project site.
- Demolition/Construction Waste - Site is required to provide containment for waste prior to and during demolition/construction. Solid waste roll off boxes and/or metal dumpsters shall be supplied by City to permitted contractor(s) only.

Parking Analysis:

Proposed Improvements:	25,080 SF Building
New Required Parking:	26...1 Space per 1000 SF Wholesale operation
26...Total Required	
New Provided Parking:	25...Straight in Parking
2...ADA Parking w/Van Accessible	
27...Total Provided	

Fire Lane Striping:


All curbs and curb ends designated as fire lanes on plans shall be painted red with 4" white lettering stating "FIRE LANE-NO PARKING-TOW AWAY ZONE". Wording may not be spaced more than 15' apart.

■ FIRE LANE ■ NO PARKING ■ TOW AWAY ZONE ■




Legend:

Existing Conditions	Proposed Construction
--- S-E ---	Easements
--- S ---	Sewer Service Lines
--- W ---	Water Lines
--- W ---	Water Service Lines
--- AE ---	Overhead Electrical
--- UE ---	Underground Electrical
--- S ---	Silt Fence
--- S ---	Chain Link Fence
--- S ---	Wood Fence
--- S ---	Telephone
--- S ---	Existing Contour
--- S ---	Proposed Contour
--- S ---	Water Meter
--- S ---	Sanitary Sewer Manhole
--- S ---	Hydrant
--- S ---	Valve

- Site Specific Notes:**
- Current owner of Lot 1, Block 1 Allen Forest Phase 6 Subdivision, is Roger N. Williams and Belinda K. Williams, 1532 Baker Avenue, Bryan, TX, 77803.
 - Current Zoning is C3 - Commercial.
 - Current use - Vacant.
 - Proposed use and improvements: Electrical Wholesale Supply along with; parking, utilities, & landscaping.
 - This lot is partially within the 100-YR floodplain according to the DFIRM for Brazos County, Texas and Incorporated areas, Map No. 48041C0215F, effective April 2, 2014.
 - Total lot acreage is 2.908 Acres. Total disturbed land is 2.908 Acres.
 - Front building setback lines of 25', side building setback lines of 15', and rear building setback line of 7.5' apply to this lot.
 - Developer/Tenant to submit electrical load information when requesting electrical service from BTU. Contact Line Design @ 821-5770.
 - All building tenants shall use dumpster facilities located by the south end of the building.



- Erosion Control Notes:**
- Erosion control measures shown in these plans shall be considered the very minimum required. It shall be the responsibility of the contractor to implement all other erosion control measures (diversion berms, drainage structures, swales, additional fencing, etc.) necessary to keep the existing improvements and developments from damage of any kind during all phases of demolition and construction.
 - The site operator, or his representative established by a letter of delegation shall make a visual inspection of all siltation controls and newly stabilized areas on a daily basis; especially after a rainfall to insure that all controls are maintained and properly functioning. Any damaged controls shall be repaired or replaced prior to the end of the work day, including re-seeding and mulching or re-sodding, if necessary.
 - All sediment trapping devices shall be installed as soon as practical after the area has been disturbed. All sediment trapping devices shall be cleaned when sediment level reaches 25% capacity. Sediment shall be disposed of by spreading on site or hauling away if not suitable for fill.
 - During construction, contractor shall maintain best management practice (bmp). Sediment fence, hay bale barriers, or other devices shall control all storm water leaving the site.
 - The contractor shall be responsible for establishing temporary erosion control measures as required for different phases of construction. Erosion control measures shown may need to be adjusted to handle increased or concentrated flows created by various stages of construction.
 - Phase II erosion control measures shall be implemented immediately after construction of their associated improvements. Inlet protection barriers shall be constructed with hay bales or silt fencing. Inlets located in paved areas shall be protected with sand bags, replacing the hay bales or silt fencing once the pavement is in place. Erosion control measures shall be kept in place until upstream drainage areas are fully stabilized.
 - The contractor is responsible for removing sediment control devices after the site has been seeded and/or sodded, and ground cover has taken root.
 - The contractor shall take all necessary measures to ensure that all disturbed areas are stabilized. Designated areas shall be block sodded and all other areas disturbed due to construction shall be hydro-mulched seeded. These stabilized areas shall be sodded or seeded, fertilized, and watered to establish a solid ground cover within 30 days of completion or if activities cease for 14 days.
 - When hydro-mulching is required, contractor shall keep mulch moist after installation and until area shows growth.
 - Erosion control measures shall be implemented prior to any excavation or demolition work.



NOTICE!

The contractor is specifically cautioned that the location and/or elevation of the existing utilities as shown on these plans is based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied upon as being exact or complete. It is the contractor's responsibility to avoid all existing utilities and repair any damaged lines, at his own expense, whether the utility is shown on these plans or not. The contractor shall notify the appropriate utility company 48 hours prior to any excavation.

Contact Information:

Texas One Call:	800-245-4545
Lone Star One Call:	800-889-8344
Texas Excavation Safety System (Digitex):	800-344-8377
Bryan Texas Utilities:	979-821-5865
Atmos Energy:	979-774-2506
Verizon:	979-821-4300
Suddenlink:	979-848-2229

Site Plan

General Notes:

- The topography shown is from field survey data.
- All utilities shown are taken from the best available information based on construction utility documents obtained by J4 Engineering from City and independent agencies and/or above ground field evidence. Shown positions may not represent as-built conditions.
- The contractor shall be responsible for verifying the exact location of all existing underground utilities, whether shown on these plans or not. Notification of the utility companies 48 hours in advance of construction is required.
- Contractor is responsible for field verifying existing and proposed grades prior to any construction and reporting any inconsistencies to the Owner.
- All construction shall be in accordance with the current BCS Standard Specifications, Details, and Design Guidelines for Water, Sewer, Streets, and Drainage, unless otherwise noted.
- All signage will need to meet the requirements of the City of Bryan Sign Ordinance.
- It is the intent of these plans to comply with all City of Bryan guidelines, details & specifications.
- See CI - General Notes.

Preliminary Plans Only
Not for Construction

This document is released for the purpose of interim review under the authority of Glenn Jones, P.E. 97800 on July 22, 2015. It is not to be used for construction, bidding, or permitting purposes.

Released for Review

No.	Revision/Issue	Date

Firm Name and Address:

J4 Engineering
PO Box 5192 - Bryan, Texas - 77805
979-739-0567 www.J4Engineering.com
Firm# 9951

Project Name and Address:

Crawford Electric
2795 Osborn Lane
Lot 1, Block 1
Allen Forest Phase 6
Subdivision ~ 2.908 AC
Bryan, Brazos County, Texas

Date: **July 2015**

Scale: **As Noted**

Sheet: **C2**

Landscape Analysis:

Construction Activities:	
Parking & Pavement	= 50,255 SF
Building	= 25,080 SF
Net Total	= 75,335 SF
Requirements:	
Building, Parking, & Pavement	= 11,300 SF
75,335 SF @ 15%	= 11,300 SF
Net Total	= 11,300 SF
Provided:	
Canopy Trees	= 5,950 SF
17 @ 350 SF	
Non-Canopy Trees	= 5,250 SF
35 @ 150 SF	
Shrubs	= 100 SF
10 @ 10 SF	
Net Total	= 11,300 SF


Symbol	Qty.	Common Name	Botanical Name	Size
	28	Live Oak	Quercus Virginiana	4" cal.
	38	Crepe Myrtle	Lagerstroemia indica	1 1/2" cal.
	10	Waxleaf Ligustrum	Ligustrum japonicum	5 gal
	--	Bermuda Grass	Cynodon Dactylon	--

Landscape Notes:


- All disturbed area to be seeded with Bermuda Grass except where Bermuda Grass Sod is called for on the plans.
- "Cal." indicates caliper at 12" above the ground.
- All trees shall be provided as container grown trees.
- All landscaping plant material shall be guaranteed for a period of one year from the date of installation by contractor. After one year, the owner will be responsible for maintenance of all landscaping.
- Plant material shown here is represented at its mature size. Plants to be installed will be significantly smaller than those shown and should not be expected to reach maturity for several years dependant on growing conditions.
- Contractor is to seed all disturbed areas left unpaved and guarantee coverage of vegetation until establishment of grass. Grass type shall be Bermuda grass or Rye/Bermuda mixture.
- Plant material will be watered by irrigation system.

Notes:

- All lumber shall be weather-resistant cedar.
- Pickets are to be 1x6, dog-eared, fastened w/ 1 1/2" galv. screws, min 2 per connection. Pickets shall be dried for 30 days prior to application of 2 coats of stain.
- Rails (4) to be 2x4 fastened w/ 3" galv. screws, min. 3 per connection.
- Posts are to be 8 gauge, 2 1/2" (Min.) metal posts placed 6' O.C., and set in 3,000 psi concrete. Galvanized caps shall be installed on each post.




Screen Fence
N.T.S.



- Notes:**
- Container grown plants only.
 - Remove containers from plants before installing.
 - Place plants in prepared bed as shown.
 - Edge spacing for plants varies with species and location.


Shrub Planting
N.T.S.



Notes:

- Trees to be balled and burlapped or container grown.
- If container grown, remove container from tree before planting.
- Top of root ball to be 3" higher than final grade.
- Top of root ball to be exposed.
- Fully remove native soil to the size of container.
- Fully remove all construction debris, trash, rocks and any other material greater than 2" in diameter.
- Install premixed soil containing 40% sandyloam topsoil, 40% black humus and 20% sharp sand.
- Dig planting hole width 12" larger than rootball on all sides.
- Scarify root ball.
- Root flare shall be exposed.

Tree Staking & Planting
N.T.S.



Landscape Plan

General Notes:

- See Sheet C1-General Notes.
- It is the intent of these plans to comply with all City of Bryan guidelines, specifications, & details.

No.	Revision/Issue	Date

Firm Name and Address:

J4 Engineering
 PO Box 5192 - Bryan, Texas - 77805
 979-739-0567 www.J4Engineering.com
 Firm# 9951

Project Name and Address:
Crawford Electric
 2795 Osborn Lane
 Lot 1, Block 1
 Allen Forest Phase 6
 Subdivision ~ 2.908 AC
 Bryan, Brazos County, Texas

Date:	July 2015	Sheet:	L1
Scale:	As Noted		

AW 29 2015