

GROESBECK STREET) VICINITY MAP

(NOT TO SCALE)

PROJECT IDENTIFICATION: PROJECT NAME: SOS MINISTRIES PHASE II. LOCATION: 1700 GROESBECK LEGAL DESCRIPTION: LOT 2, BLOCK 1, SAVE OUR STREETS

TOTAL SITE AREA TO BE DISTURBED IS: 2.34 ACRES.

PD-M) DISTRICT, AS APPROVED BY THE BRYAN CITY COUNCIL ON NOVEMBER 25, 2008 (ORDINANCE NO. ___); ALL DEVELOPMENT ON THIS PROPERTY SHALL BE IN ACCORDANCE WITH THE SPECIFIC DEVELOPMENT REQUIREMENTS FOR THE

. PROPOSED USE & IMPROVEMENTS: 5,000 SQ.FT. & 3,750 SQ.FT. MIXED USE CENTER, WATER, SANITARY SEWER AND

FLOOD INSURANCE RATE MAP FOR BRAZOS COUNTY, TEXAS AND INCORPORATED AREAS. COMMUNITY NO. 480082, PANEL NO 0141C, MAP NO. 48041C0141C. EFFECTIVE DATE: JULY 2,

LINES, TV/CABLE, COMMUNICATIONS LINES, etc. SHALL BE UNDERGROUND INSTALLATIONS AND INSTALLED TO CITY OF

10. BUILDING AREA: 5,000 SQ.FT. & 3,750 SQ.FT. DIMENSIONS ARE MEASURED TO FACE OF CURB UNLESS

. ALL DISTURBED EARTH MUST BE 100% COVERED WITH ESTABLISHED GRASS OR GROUND COVER PRIOR TO CERTIFICATE

13. ALL BACK FLOW DEVICES MUST BE INSTALLED AND TESTED

14. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSTALLATION OF ALL FRANCHISE & PR GENERAL CONTRACTOR IS RESPONSIBLE FOR FURNISHING & INSTALLING ANY NECESSARY UTILITY CONDUIT PRIOR TO SUBGRADE PREPARATION & PAVING OPERATION. GENERAL CONTRACTOR IS RESPONSIBLE FOR DETERMINATION OF UTILITY INSTALLATION ORDER.

15. ALL ROOF AND GROUND MOUNTED MECHANICAL EQUIPMENT SHALL BE SCREENED FROM VIEW FROM ANY PUBLIC RIGHT-OF-WAY OR RESIDENTIAL DISTRICT WITHIN 150' OF THE SUBJECT LOT. SUCH SCREENING SHALL BE COORDINATED WITH BUILDING ARCHITECTURE.

16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTAINMENT AND PROPER DISPOSAL OF ALL LIQUID AND SOLID WASTE ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL USE ALL MEANS NECESSARY TO PREVENT THE OCCURRENCE OF WIND BLOWN LITTER FROM THE PROJECT SITE.


17. DEMOLITION / CONSTRUCTION WASTE: SITE IS REQUIRED TO PROVIDE CONTAINMENT FOR WASTE PRIOR TO AND DURING DEMOLITION / CONSTRUCTION. SOLID WASTE ROLL OFF BOXES AND/OR METAL DUMPSTERS SHALL BE SUPPLIED BY CITY OR CITY PERMITTED CONTRACTOR(S) ONLY.

18. CONTRACTOR IS RESPONSIBLE FOR COORDINATING TEMPORARY WATER OUTAGE WITH ADJACENT & AFFECTED PROPERTIES AS WELL AS WITH CITY OF BRYAN WATER SERVICES.


0 4 2


2


N TANT



SHEET NO.







DESCRIPTION OF CONTROLS

EROSION AND SEDIMENT CONTROL:
1. SILT FENCE
2. ROCK CONSTRUCTION ENTRANCE
3. SEDIMENT TRAP

INSTALL EROSION & SEDIMENT CONTROL DEVICES PER DETAILS HEREON. SEDIMENT MUST BE REMOVED FROM SEDIMENT CONTROL DEVICES PRIOR TO SEDIMENT

REACHING 1/2 THE HEIGHT OF THE DEVICE OR STRUCTURE. IF SEDIMENT ESCAPES FROM THE SITE AREA, ACCUMULATIONS MUST BE REMOVED AT A FREQUENCY TO MINIMIZE FURTHER NEGATIVE EFFECTS, AND WHENEVER FEASIBLE, PRIOR TO THE NEXT RAIN EVENT.

STABILIZATION PRACTICES:
TEMPORARY STABILIZATION: ALL STOCK PILED AND OTHER DISTURBED AREAS WHERE
CONSTRUCTION ACTIVITIES TEMPORARILY CEASE FOR AT LEAST 21 DAYS WILL BE SEEDED
NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN THAT AREA.

PERMANENT STABILIZATION: ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASE SHALL BE SODDED OR HYDROMULCH SEEDED (AS PER PLAN) FOR PERMANENT EROSION CONTROL NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN ACCORDANCE WITH TXDOT 162/164. PRIOR TO FINAL REVEGETATION, CONTRACTOR IS TO REPLACE TOPSOIL TO A DEPTH OF 6". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED.

HYDROMULCH: TO BE "EXCEL FIBERMULCH II W/ TACKIFIER - APPLICATION RATE OF 2500 LBS/ACRE. GRASS SEED AND FERTILIZER TO BE INCORPORATED INTO SLURRY.
GRASS SEED MIX: SUMMER-HULLED COMMON BERMUDA GRASS, MIN. 85% PURE
LIVE SEED © 90 Ibs. PER ACRE.
WINTER-UNHULLED COMMON BERMUDA GRASS, MIN. 85% PURE LIVE SEED ©
90 Ibs. PER ACRE + ANNUAL RYE GRASS, MIN. 85% PURE LIVE SEED ©
175 Ibs.
PER ACRE.

REPLANTING, MOVING, MAINTAINING OF EXISTING GRADES, AND REPAIR OF ANY EROSION DAMAGES FOR ALL AREAS WHERE SEEDING AND MULCHING WORK IS COMPLETED. MAINTENANCE TO BE CONDUCTED DURING THE PLANTING PERIOD THRU 90 DAYS AFTER

FERTILIZER: 3-1-2 RATIO FERTILIZER W/ SULFUR & TRACE ELEMENTS ● 350

GUARANTEE: CONTRACTOR IS RESPONSIBLE FOR WATERING, MAINTENANCE AND ESTABLISHMENT OF GRASS FOR A PERIOD OF 90 DAYS AFTER FINAL REVEGETATION APPLICATION FOR PERMANENT EROSION CONTROL. CONTRACTOR IS TO GUARANTEE ALL PLANTED MATERIAL GROWTH AND COVERAGE FOR A PERIOD OF 6 MONTHS, GROWTH AND COVERAGE SHALL BE DEFINED AS 95% OF THE PLANTED AREA WITH UNIFORM COVERAGE OF CRASS CREATER THAN 1" IN 1950 CREATER THAN 1." OF GRASS GREATER THAN 1" IN HEIGHT WITH NO BARE SPOTS GREATER THAN 2

-PROVIDE A SECOND APPLICATION OF SPECIFIED SOD OR HYDROMULCH SEEDING (AS PER PLAN) TO BARE AREAS NOT MEETING SPECIFIED COVERAGE — TO BE PERFORMED WITHIN 60 DAYS OF INITIAL APPLICATION AND IMMEDIATELY UPON NOTIFICATION BY THE

RECORD KEEPING: CONTRACTOR IS RESPONSIBLE FOR RECORDING & MAINTAINING THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR
 DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE. 3. DATES WHEN STABILIZATION MEASURES ARE INITIATED.

RECORDS MUST BE KEPT WITH THE SWP3 AND MADE READILY AVAILABLE UPON REQUEST TO THE PARTIES IN PART III.D.1 OF THE TPDES GENERAL PERMIT TXR150000.

STRUCTURAL CONTROL PRACTICES:
TEMPORARY EROSION CONTROLS TO INCLUDE INSTALLATION OF SILT FENCE, GRAVEL
FILTER BAGS AND CONSTRUCTION ENTRANCE(S). CONTRACTOR SHALL PREVENT
TRANSPORT OF SEDIMENT TO DOWNSTREAM AREAS AND IS RESPONSIBLE FOR CLEANUP
AND RESTORATION IF SUCH OCCUR.

SILT FENCE TO BE INSTALLED PER DETAIL AT TOE OF DOWNHILL SLOPES/STOCKPILES AS SHOWN ON PLAN. HAY BALE CHECK STRUCTURES (IF NEEDED) ARE TO BE INSTALLED PER PLAN AT UPSTREAM END OF OUTLET WORKS. ALL EROSION CONTROL DEVICES ARE TO BE MAINTAINED UNTIL ESTABLISHMENT OF GRASS OCCURS.

PERMANENT STORM WATER CONTROLS: STORM WATER WILL DRAIN TO THE PROJECT SPECIFIC DETENTION POND AND DRAINAGE FACILITY. STORM WATER DETENTION WILL BE PROVIDED ON—SITE AS SHOWN HEREON.

OTHER CONTROLS:
OFFSITE VEHICLE TRACKING:
CONTRACTOR IS TO INSURE NO CONSTRUCTION DEBRIS OR MUD IS TRACKED OR
DISCARDED ONTO ANY PUBLIC OR PRIVATE STREETS OR LANDS AND IS RESPONSIBLE
FOR CLEANUP AFTER EACH DAYS WORK, INSTALL ROCK CONSTRUCTION ENTRANCE AS
INDICATED WITH CURP PROTECTION. CONTRACTOR IS RESPONSIBLE TO RESTORE ANY

WASTE MATERIALS:
ALL WASTE MATERIALS ARE TO BECOME PROPERTY OF THE CONTRACTOR AND ARE TO E
REMOVED AND DISPOSED OF OFF-SITE. NO ON-SITE BURYING OF WASTE MATERIALS IS
ALLOWED. AT THE END OF EACH WORKING DAY, THE CONTRACTOR SHALL GATHER AND
COLLECT ALL RUBBISH AND DEBRIS AND STORE IN AN ACCEPTABLE MANNER WHICH
PREVENTS MATERIALS FROM BEING BLOWN OR OTHERWISE REDISTRIBUTED ACROSS THE
SITE OR ADJACENT LANDS OR WATER COURSES.

HAZARDOUS WASTE: ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF AS PER LOCAL OR STATE REGULATIONS AND IN ACCORDANCE WITH MFR'S SPECIFICATIONS.

TIMING OF CONTROLS/MEASURES > INSTALL SILT FENCING. INSTALL GRAVEL FILTER BAGS

> INSTALL ROCK CONSTRUCTION ENTRANCE(S)
> DISTURBED AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN 21 DAYS ARE TO BE STABILIZED WITH HYDROMULCH SEEDING OR BROADCAST SEEDING (AS PER PLAN) NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN THAT AREA.

> DURING CLEARING/GRADING ACTIVITIES, SEDIMENT COLLECTING AT CHECK STRUCTURES AND SILT FENCE SHALL BE REMOVED AS IT REACHES 1/2 THE HEIGHT OF THE

STRUCTURE.

> ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASE SHALL
BE HYDROMULCH SEEDED OR BROADCAST SEEDED (AS PER PLAN) FOR PERMANENT
EROSION CONTROL NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY. IN THE EVENT OF FLOODING OR OTHER UNCONTROLLABLE SITUATIONS WHICH PROHIBIT ACCESS TO THE INSPECTION SITES, INSPECTIONS MUST BE CONDUCTED AS SOON AS

CONTRACTOR PERSONNEL FAMILIAR WITH THE SWP3 MUST INSPECT DISTURBED AREAS THAT HAVE NOT BEEN FINALLY STABILIZED, AREAS USED FOR STORAGE OF MATERIALS EXPOSED TO PRECIPITATION, AND STRUCTURAL CONTROLS FOR EVIDENCE OF, OR POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. SEDIMENT & EROSION CONTROL DEVICES MUST BE INSPECTED TO ENSURE PROPER OPERATION. VEHICLE ENTRANCE/EXIT LOCATIONS MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIME

INSPECTIONS MUST BE CONDUCTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS OR ONCE EVERY FOURTEEN (14) CALENDAR DAYS AND WITHIN TWENTY FOUR (24) HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. THE SWP3 MUST BE MODIFIED BASED ON RESULTS OF INSPECTIONS, AS NECESSARY, TO BETTER CONTROL POLLUTANTS IN RUNOFF. REVISIONS TO THE SWP3 TO BE COMPLETED WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE INSPECTION IN ACCORDANCE WITH THE TPDES GENERAL PERMIT.

A REPORT IN ACCORDANCE WITH THE TPDES GENERAL PERMIT MUST BE MAINTAINED BY THE CONTRACTOR AND RETAINED AS PART OF THE SWP3.

CERTIFICATIONS & RESPONSIBLE PARTIES

CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE, AND LOCAL REGULATIONS

THIS EROSION CONTROL AND STORM WATER POLLUTION PREVENTION PLAN HAS BEEN PREPARED IN ACCORDANCE WITH CURRENT: CITY OF BRYAN DRAINAGE POLICY, CITY OF BRYAN STORM WATER POLLUTION PREVENTION POLICY, EPA REQUIREMENTS FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER A NPDES GENERAL PERMIT, USACE 33 CFR, & SECTION 404 OF THE CLEAN WATER ACT & TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM (TPDES) GENERAL PERMIT No. TXR150000 AS ADMINISTERED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ). NON-STORM WATER DISCHARGES: -NONE EXPECTED-

MAINTENANCE/INSPECTION PROCEDURES

EROSION AND SEDIMENT CONTROL INSPECTION AND MAINTENANCE PRACTICES: >ALL CONTROL MEASURES TO BE INSPECTED BY CONTRACTOR AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS OR ONCE EVERY FOURTEEN (14) CALENDAR DAYS AND WITHIN TWENTY FOUR (24) HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER >MAINTAIN RECORDS AND REPORTS ACCORDING TO EPA CONSTRUCTION GENERAL PERMIT CHECKLIST. >ALL MEASURES SHALL BE MAINTAINED IN GOOD WORKING ORDER WITH REPAIR BEING INITIATED WITHIN 24 HOURS OF REPORT. >BUILT UP SEDIMENT SHALL BE REMOVED FROM CHECK STRUCTURES AND SILT FENCE WHEN IT HAS REACHED $\frac{1}{2}$ THE HEIGHT OF THE >SILT FENCE AND HAY BALES TO BE INSPECTED FOR PROPER INSTALLATION AND THAT NO PIPING OR UNDERMINING IS OCCURRING.
>TEMPORARY SEEDING TO BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND COVERAGE — RE—SEED AS NECESSARY
>PERMANENT HYDROMULCH SEEDING & SODDING TO BE INSPECTED PER GUARANTEE.

SIGNATURE	FOR	RESPONSIBLE FOR
(NAME, TITLE, & DATE)	(COMPANY & ADDRESS)	
		CLEARING
		TEMPORARY CONTROLS & STABILIZATION
		PERMANENT STABILIZATION (RE-VEGETATION)


N Z Z Z

D U R ENGINE TEXA YAN, TE YYN, (979 XX: (979 GISTRA]


S.S. BR TE


O 4; C


SHEET NO.





0 ë 6











PERSONAL TERRETORIAN AND TERRETORIAN CONTINUES OF CONTINUES OF CONTINUES OF CONTINUES OF CONTINUES OF CONTINUES

N C TANT PE A D O d.b.a. (410 SEWER DETAILS
Y SEWER SERVIC
0+00 THRU 5+00 SANITARY SANITARY STATION OF

C5.3