

VICINITY MAP

LEGEND

[Pattern]	EXISTING BUILDING
[Pattern]	PROPOSED 4" CONCRETE SIDEWALK
[Pattern]	PROPOSED 5" CONCRETE PAVEMENT
[Pattern]	PROPOSED 7" CONCRETE PAVEMENT
[Pattern]	100-YEAR FLOODPLAIN
[Pattern]	FLOODWAY
[Line]	HUDSON CREEK CENTERLINE
[Line]	PROPERTY LINE
[Line]	ADJACENT PROPERTY LINE
[Line]	BUILDING SETBACK LINE
[Line]	EXISTING PAVEMENT EDGE
[Line]	EXISTING MAJOR CONTOURS
[Line]	EXISTING MINOR CONTOURS
[Line]	PROPOSED MAJOR CONTOURS
[Line]	PROPOSED MINOR CONTOURS
[Symbol]	SILT FENCE, INSTALLED PER DETAIL B/C/S SWPP DETAIL
[Symbol]	CONSTRUCTION ENTRANCE, INSTALLED PER B/C/S SWPP DETAIL

SITE PLAN FOR:
SAM HOUSTON ELEMENTARY SCHOOL
4501 CANTERBURY DR.
BRYAN, TX 77802-5906

LEGAL DESCRIPTION:
COPPERFIELD PF4, BLOCK 14, LOT 1,
12.0 ACRES
SAM HOUSTON ELEMENTARY

ZONING: PLANNED DEVELOPMENT
MISCELLANEOUS COMMERCIAL, CMSC

TOTAL AREA DISTURBED: 2.53 ACRES

A PORTION OF THE PROPERTY IS LOCATED WITHIN
THE 100-YR FLOODPLAIN.

OWNER:
BRYAN I.S.D.
101 NORTH TEXAS AVENUE
BRYAN, TX 77803
TELEPHONE: 979-209-7062
CONTACT: JEFF WINDSOR
EMAIL: JEFF.WINDSOR@BRYANISD.ORG

- EROSION CONTROL NOTES:**
- THE CONTRACTOR SHALL PROVIDE EROSION PROTECTION AT ALL LOCATIONS OF CONSTRUCTION.
 - THE CONTRACTOR WILL REMOVE ALL EXCESS SOIL FROM CONSTRUCTION VEHICLES PRIOR TO EXITING THE SITE.
 - THE CONTRACTOR SHALL UNDERTAKE PROPER METHODS TO REDUCE DUST GENERATION FROM THE SITE.
 - THE CONTRACTOR MUST COMPLY WITH FEDERAL, STATE, AND LOCAL REGULATIONS REGARDING SEDIMENTS AND EROSION CONTROL.
 - A COPY OF THIS PLAN MUST BE KEPT AT THE CONSTRUCTION FACILITY DURING THE ENTIRE CONSTRUCTION PERIOD.
 - ALL FINISHED GRADES ARE TO BE HYDRO-MULCHED, SPOT SODDED OR SEEDED AND WATERED UNTIL GROWTH IS ESTABLISHED.


- SITE PLAN NOTES:**
- CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN THESE PLANS AND ONSITE FIELD CONDITIONS OR SPECIFICATIONS OF OTHER DISCIPLINES
 - THE CONTRACTOR IS REQUIRED TO OBTAIN ALL NECESSARY PERMITS, AS WELL AS INSPECTION APPROVALS.
 - A COPY OF APPROVED CONSTRUCTION PLANS SHALL BE KEPT ON SITE AT ALL TIMES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL MAINTAIN A SET OF REDLINE DRAWINGS TO RECORD AS-BUILT CONDITIONS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTAINMENT AND PROPER DISPOSAL OF ALL LIQUID AND SOLID WASTE ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL USE ALL MEANS NECESSARY TO PREVENT THE OCCURRENCE OF WIND BLOWN LITTER FROM THE PROJECT SITE.
 - DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AN ORDERLY PROJECT SITE. THE CONTRACTOR SHALL CLEAN AND REMOVE ANY SURPLUS OR DISCARDED MATERIALS, TEMPORARY STRUCTURES, AND DEBRIS FROM THE PROJECT SITE.
 - THE CONTRACTOR IS RESPONSIBLE FOR STORAGE AND SAFE-GUARDING OF ALL MATERIALS AND EQUIPMENT AT THE PROJECT SITE TO MAINTAIN A SAFE AND SECURE PROJECT.
 - THE CONTRACTOR SHALL COORDINATE SITE STORAGE WITH THE OWNER TO NOT OBSTRUCT DRIVES, ACCESS, OR OTHER OPERATIONAL REQUIREMENTS.
 - ANY ADJACENT RIGHT-OF-WAY (R.O.W.) OR PROPERTY AFFECTED DURING CONSTRUCTION, SHALL BE RETURNED TO PRE-CONSTRUCTION CONDITION AT THE CONTRACTOR'S EXPENSE.
 - THE CONTRACTOR SHALL PROTECT ALL SURVEY MONUMENTATION, BENCHMARKS, AND MARKERS DURING CONSTRUCTION.
 - THE CONTRACTOR MUST PROVIDE CONSTRUCTION STAKING SERVICES BASED ON THE INFORMATION PROVIDED IN THE PLANS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES OR SERVICE LINES DURING THE CONSTRUCTION PROCESS. WHERE EXISTING UTILITIES OR SERVICE LINES ARE DAMAGED, THE CONTRACTOR SHALL REPAIR OR REPLACE THE UTILITY OR SERVICE LINE WITH THE SAME TYPE OF MATERIAL AND CONSTRUCTION, OR BETTER. ALL MATERIAL AND LABOR SHALL BE AT THE CONTRACTOR'S EXPENSE.
 - THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL STATE AND FEDERAL REGULATIONS REGARDING CONSTRUCTION ACTIVITIES NEAR ENERGIZED OVERHEAD ELECTRIC LINES.
 - THE CONTRACTOR ACKNOWLEDGES THAT THE LOCATION AND/OR ELEVATION OF THE EXISTING UTILITIES SHOWN ON THE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, CITY MAPS AND, WHEN POSSIBLE, FIELD MEASUREMENTS. THE INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE.
 - THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE UTILITY COMPANY 48 HOURS PRIOR TO EXCAVATION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS.
 - THE SCOPE OF THIS PROJECT INCLUDES SIDEWALKS, AN ADDITIONAL PARKING LOT, SITE GRADING TO MEET ADA STANDARDS, PROVIDING POSITIVE DRAINAGE THROUGHOUT THE SITE, AND PAVING AND JOINT LAYOUTS BASED ON THE GEOTECHNICAL RECOMMENDATIONS FOR THE SITE.
 - NOTE: DEMOLITION/CONSTRUCTION WASTE - SITE IS REQUIRED TO PROVIDE CONTAINMENT FOR WASTE PRIOR TO AND DURING DEMOLITION/CONSTRUCTION. SOLID WASTE ROLL OFF BOXES AND/OR METAL DUMPSTERS SHALL BE SUPPLIED BY CITY OR CITY PERMITTED CONTRACTOR(S) ONLY.



GESSNER ENGINEERING
Corporate Office
2501 Ashford Drive
Suite 102
College Station, Texas 77840
www.gessnerengineering.com

FORM REGISTRATION NUMBER:
TBPE F-7451, TBPLS F-10193910

COLLEGE STATION 979.680.8840
BRENNAM 979.836.6855
FORT WORTH 817.405.0774
SAN ANTONIO 210.556.4124



PRELIMINARY NOT FOR CONSTRUCTION

**SAM HOUSTON ELEMENTARY
BRYAN, TX 77802**

SITE PLAN

Issue Date: 03/30/2016
Drawn By: PR
Checked By: ASP
Project Number: 15-1051

Revisions:

△	
△	
△	
△	

C1.0