GOVERNING SPECIFICATIONS

BRYAN/COLLEGE STATION 2012 UNIFIED DESIGN GUIDELINES, MANUALS, TECHNICAL SPECIFICATIONS, & STANDARD CONSTRUCTION DETAILS

SITE PLANS FOR COLONY COMMERCIAL L-2 B-1 PHYSICIAN'S ER

LOT 2, BLOCK 1
COLONY COMMERCIAL SUBDIVISION
JOHN AUSTIN SURVEY, A-2
BRYAN, BRAZOS COUNTY, TEXAS


MAY, 2016

INDEX OF SHEETS

SHEET	TITLE	#
	CIVIL SITE PLAN COVER PAGE	1
C1.1	SITE PLAN	2
C2.1	EROSION CONTROL PLAN	3
C3.1	GRADING PLAN	4
C4.1	LANDSCAPE PLAN	5
C5.1	NOTES AND DETAILS	6

OWNED BY:
CARRABBA INTERESTS
C/O MR. MARK CARRABBA
P.O. BOX 663
BRYAN, TX 77806

DEVELOPED BY:
GULFTEX PROPERTIES, INC.
6000 STAPLES, SUITE 205
CORPUS CHRISTI, TEXAS 78413
(361) 992-9700 EXT. 16




MAY 18 2016

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF ALFRED A. PAINE, P.E. 97221 ON 5/18/2016 FOR THE PURPOSE OF INTERIM REVIEW. -NOT FOR CONSTRUCTION-

ENGINEER:




DON DURDEN, INC d.b.a. CIVIL ENGINEERING CONSULTANTS 4101 S. TEXAS AVE, SUITE A BRYAN, TEXAS 77802 TEL: (979) 846-6212 FAX: (979) 846-8252 REGISTRATION #F-2214



D U R D E N , ENGINEERING COI . TEXAS AVE, \$ RYAN, TEXAS 778 EL: (979) 846-62 AX: (979) 846-82 GISTRATION #F-2

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF ALFRED A. PAINE, P.E. 97221 ON 5/18/2016 FOR THE PURPOSE OF INTERIM REVIEW. -NOT FOR CONSTRUCTION-

SHEET NO.



DESCRIPTION OF CONTROLS

INSTALL EROSION & SEDIMENT CONTROL DEVICES PER DETAILS HEREON. SEDIMENT MUST BE REMOVED FROM SEDIMENT CONTROL DEVICES PRIOR TO SEDIMENT REACHING 1/2 THE HEIGHT OF THE DEVICE OR STRUCTURE.

IF SEDIMENT ESCAPES FROM THE SITE AREA, ACCUMULATIONS MUST BE REMOVED AT A FREQUENCY TO MINIMIZE FURTHER NEGATIVE EFFECTS, AND WHENEVER FEASIBLE, PRIOR TO THE NEXT RAIN EVENT.

STABILIZATION PRACTICES:
TEMPORARY STABILIZATION: ALL STOCK PILED AND OTHER DISTURBED AREAS
WHERE CONSTRUCTION ACTIVITIES TEMPORARILY CEASE FOR AT LEAST 21 DAYS
WILL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION
ACTIVITY IN THAT AREA.

PERMANENT STABILIZATION: ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASE SHALL BE SODDED OR HYDROMULCH SEEDED (AS PER PLAN) FOR PERMANENT EROSION CONTROL NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN ACCORDANCE WITH TXDOT 162/164 PRIOR TO FINAL REVEGETATION, CONTRACTOR IS TO REPLACE TOPSOIL TO A DEPTH OF 6". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED.

HYDROMULCH: TO BE "EXCEL FIBERMULCH II W/ TACKIFIER - APPLICATION RATE OF 2500 LBS/ACRE. GRASS SEED AND FERTILIZER TO BE INCORPORATED INTO SLURRY.

GRASS SEED MIX: SUMMER-HULLED COMMON BERMUDA GRASS, MIN. 85% PURE LIVE SEED © 90 Ibs. PER ACRE.

WINTER-UNHULLED COMMON BERMUDA GRASS, MIN. 85% PURE LIVE SEED © 90 Ibs. PER ACRE + ANNUAL RYE GRASS, MIN. 85% PURE LIVE SEED © 175 Ibs. TERTILIZER: 3-1-2 RATIO FERTILIZER W/ SULFUR & TRACE ELEMENTS • 350

MAINTENANCE: SHALL CONSIST OF WEEDING, FERTILIZING, INSECT CONTROL, WATERING, REPLANTING, MOVING, MAINTAINING OF EXISTING GRADES, AND REPAIR OF ANY EROSION DAMAGES FOR ALL AREAS WHERE SEEDING AND MULCHING WORK IS COMPLETED. MAINTENANCE TO BE CONDUCTED DURING THE PLANTING PERIOD THRU 90 DAYS AFTER THE WORK IS COMPLETED, INSPECTED AND APPROVED BY THE ENGINEER AND OWNER.

GUARANTEE: CONTRACTOR IS RESPONSIBLE FOR WATERING, MAINTENANCE AND ESTABLISHMENT OF GRASS FOR A PERIOD OF 90 DAYS AFTER FINAL REVEGETATION APPLICATION FOR PERMANENT EROSION CONTROL. CONTRACTOR IS TO GUARANTEE ALL PLANTED MATERIAL GROWTH AND COVERAGE FOR A PERIOD OF 6 MONTHS. GROWTH AND COVERAGE SHALL BE DEFINED AS 95% OF THE PLANTED AREA WITH UNIFORM COVERAGE OF GRASS GREATER THAN 1" IN HEIGHT WITH NO BARE SPOTS GREATER THAN 2 SQUARE FEET.

-PROVIDE A SECOND APPLICATION OF SPECIFIED SOD OR HYDROMULCH SEEDING (AS PER PLAN) TO BARE AREAS NOT MEETING SPECIFIED COVERAGE — TO BE PERFORMED WITHIN 60 DAYS OF INITIAL APPLICATION AND IMMEDIATELY UPON NOTIFICATION BY THE ENGINEER TO REPLANT.

RECORD KEEPING: CONTRACTOR IS RESPONSIBLE FOR RECORDING & MAINTAINING THE FOLLOWING:

1. DATES WHEN MAJOR GRADING ACTIVITIES OCCUR
2. DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE.

3. DATES WHEN STABILIZATION MEASURES ARE INITIATED.

STRUCTURAL CONTROL PRACTICES: TEMPORARY EROSION CONTROLS TO INCLUDE INSTALLATION OF SILT FENCE, GRAVEL FILTER BAGS AND CONSTRUCTION ENTRANCE(S). CONTRACTOR SHALL PREVENT TRANSPORT OF SEDIMENT TO DOWNSTREAM AREAS AND IS RESPONSIBLE FOR CLEANUP AND RESTORATION IF SUCH SHOULD OCCUR.

SILT FENCE TO BE INSTALLED PER DETAIL AT TOE OF DOWNHILL SLOPES AS SHOWN ON PLAN. HAY BALE CHECK STRUCTURES (IF NEEDED) ARE TO BE INSTALLED PER PLAN AT UPSTREAM END OF OUTLET WORKS. ALL EROSION CONTROL DEVICES ARE TO BE MAINTAINED UNTIL ESTABLISHMENT OF GRASS OCCURS.

PERMANENT STORM WATER CONTROLS: STORM WATER WILL DRAIN TO THE SUBDIMISION SPECIFIC DETENTION POND AND DRAINAGE FACILITY. STORM WATER DETENTION WILL BE PROVIDED OFF—SITE AS DESIGNED BY OTHERS.

OTHER CONTROLS:
OFFSITE VEHICLE TRACKING:
CONTRACTOR IS TO INSURE NO CONSTRUCTION DEBRIS OR MUD IS
TRACKED OR DISCARDED ONTO ANY PUBLIC OR PRIVATE STREETS OR
LANDS AND IS RESPONSIBLE FOR CLEANUP AFTER EACH DAYS WORK.
INSTALL ROCK CONSTRUCTION ENTRANCE AS INDICATED WITH CURB
PROTECTION. CONTRACTOR IS RESPONSIBLE TO RESTORE ANY DAMAGE
DONE TO EXISTING STREETS OR INFRASTRUCTURE.

WASTE MATERIALS:
ALL WASTE MATERIALS ARE TO BECOME PROPERTY OF THE CONTRACTOR AND ARE TO BE REMOVED AND DISPOSED OF OFF-SITE. NO ON-SITE BURYING OF WASTE MATERIALS IS ALLOWED. AT THE END OF EACH WORKING DAY, THE CONTRACTOR SHALL GATHER AND COLLECT ALL RUBBISH AND DEBRIS AND STORE IN AN ACCEPTABLE MANNER WHICH PREVENTS MATERIALS FROM BEING BLOWN OR OTHERWISE REDISTRIBUTED ACROSS THE SITE OR ADJACENT LANDS OR WATER COURSES.

HAZARDOUS WASTE: ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF AS PER LOCAL OR STATE REGULATIONS AND IN ACCORDANCE WITH MFR'S SPECIFICATIONS.

TIMING OF CONTROLS/MEASURES

> INSTALL SILT FENCING.

> INSTALL ROCK CONSTRUCTION ENTRANCE(S)

> DISTURBED AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY
CEASES FOR MORE THAN 21 DAYS ARE TO BE STABILIZED WITH HYDROMULCH SEEDING OR BROADCAST SEEDING (AS PER PLAN) NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN THAT

 DURING CLEARING/GRADING ACTIVITIES, SEDIMENT COLLECTING AT CHECK STRUCTURES AND SILT FENCE SHALL BE REMOVED AS IT REACHES 1/2 THE HEIGHT OF THE STRUCTURE.
ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES
PERMANENTLY CEASE SHALL BE HYDROMULCH SEEDED OR BROADCAST SEEDED (AS PER PLAN) FOR PERMANENT EROSION CONTROL NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY.

INSPECTION OF CONTROLS:
IN THE EVENT OF FLOODING OR OTHER UNCONTROLLABLE SITUATIONS
WHICH PROHIBIT ACCESS TO THE INSPECTION SITES, INSPECTIONS MUST BE
CONDUCTED AS SOON AS ACCESS IS PRACTICABLE.

CONTRACTOR PERSONNEL FAMILIAR WITH THE SWP3 MUST INSPECT DISTURBED AREAS THAT HAVE NOT BEEN FINALLY STABILIZED, AREAS USED FOR STORAGE OF MATERIALS EXPOSED TO PRECIPITATION, AND STRUCTURAL CONTROLS FOR EVIDENCE OF, OR POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. SEDIMENT & EROSION CONTROL DEVICES MUST BE INSPECTED TO ENSURE PROPER OPERATION. VEHICLE ENTRANCE/EXIT LOCATIONS MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.

INSPECTIONS MUST BE CONDUCTED AT LEAST ONCE EVERY SEVEN (7) CALENDER DAYS OR ONCE EVERY FOURTEEN (14) CALENDER DAYS AND WITHIN TWENTY FOUR (24) HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. THE SWP3 MUST BE MODIFIED BASED ON RESULTS OF INSPECTIONS, AS NECESSARY, TO BETTER CONTROL POLLUTANTS IN RUNOFF. REVISIONS TO

THE SWP3 TO BE COMPLETED WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE INSPECTION IN ACCORDANCE WITH THE TPDES GENERAL A REPORT IN ACCORDANCE WITH THE TPDES GENERAL PERMIT MUST BE MAINTAINED BY THE CONTRACTOR AND RETAINED AS PART OF THE SWP3.

GENERAL NOTES

1. ALL UTILITIES AND SERVICE LINES SHOWN ARE TAKEN FROM RECORD INFORMATION SUPPLIED BY THE UTILITY OWNER OR HORIZONTALLY LOCATED BY INDEPENDENT LOCATORS. CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONDITIONS PRIOR TO CONSTRUCTION. OWNER AND ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF INFORMATION OR DATA RELIED ON TO DEPICT UNDERGROUND FACILITIES. CONTRACTOR IS TO CONTACT OWNERS OF ALL UTILITIES AND SERVICE LINES WITHIN THE PROJECT AREA AND NOTIFY OF INTENT AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS. CONTRACTOR IS TO VERIFY THE EXACT LOCATION AND VERTICAL POSITIONING OF ALL PIPELINES, EXISTING UTILITIES, AND SERVICE LINES WITHIN THE PROJECT AREA WHETHER SHOWN ON THE PLANS OR NOT, AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. CONTRACTOR IS TO MAINTAIN STRUCTURAL INTEGRITY OF ALL PIPELINES, ELECTRIC TRANSMISSION POLES AND LINES, PERMANENT AND TEMPORARY UTILITIES. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DONE TO EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CLEARING/DIRTWORK EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CLEARING/DIRTWORK ACTIVITIES.

2. CONTRACTOR TO CONTACT TEXAS 811 48 HOURS PRIOR TO CONSTRUCTION. SPECIFIC ATTENTION SHOULD BE PAID TO FRANCHISE UTILITIES, VERIZON, GTE, ECT. SHOULD A CONFLICT ARISE BETWEEN THE PROPOSED CONSTRUCTION AND AN EXISTING UTILITY, CONTACT CEC 48 HOURS PRIOR TO CONSTRUCTION.

4. ALL SWALE AREAS (BOTTOM WIDTHS & SIDE SLOPES) ARE TO BE PREPARED AND HYDROMULCHED FOR PERMANENT ESTABLISHMENT OF VEGETATION. PRIOR TO HYDROMULCHING OPERATIONS, CONTRACTOR TO REPLACE TOPSOIL TO A DEPTH OF 6". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED. FINAL GRADES WITH ESTABLISHED VEGETATION SHALL BE AS CALLED OUT ON THE GRADING PLAN.

3. ALL DISTURBED AREAS NOT TO BE PAVED ARE TO HAVE ESTABLISHMENT OF GRASS AS OUTLINED IN THE DESCRIPTION OF CONTROLS, STABILIZATION PRACTICES

5. CONTRACTOR IS TO MAINTAIN EROSION CONTROL THROUGHOUT DURATION OF THE PROJECT AND UNTIL VEGETATION IS ESTABLISHED. INSURE SEDIMENT IS NOT TRANSPORTED DOWNSTREAM FROM PROJECT VIA HAY BALES, BRUSH PILE AND SILT FENCE INSTALLATIONS. IF EXCESSIVE EROSION IS OBSERVED IN THE FIELD, ADDITIONAL EROSION CONTROLS SHALL BE INSTALLED.

6. CONTRACTOR SHALL NOT ALLOW SEDIMENT TO ENTER THE DOWNSTREAM CHANNEL. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OF THE DOWNSTREAM CHANNEL AREAS AND RESTORING TO ORIGINAL CONDITION, INCLUDING ESTABLISHMENT OF REVEGETATION SHOULD CONSTRUCTION SEDIMENT BE FOUND OUTSIDE THE LIMITS OF CONSTRUCTION.

7. CONSTRUCTION EXITS AND ASSOCIATED SEDIMENT TRAPS ARE TO BE CLEANED REGULARLY, CONTRACTOR TO INSURE NO MUD IS TRACKED ON TO EXISTING CITY OR STATE ROADWAYS. IF TRACKING OCCURS CONTRACTOR IS TO INSURE THAT MUD IS NOT ALLOWED TO REMAIN BEYOND THE END OF EACH WORK DAY. 8. SEDIMENT IS TO BE CLEANED FROM SILT FENCING OR OTHER SEDIMENT CONTROL DEVICES WHEN DEPTH OF SEDIMENT REACHES ~1/2 TOTAL HEIGHT OF DEVICE. CONTRACTOR IS TO INSURE EROSION CONTROL DEVICES ARE CONSISTENTLY INSTALLED AND PROPERLY MAINTAINED.

9. IN AREAS ADJACENT TO POND AND CHANNEL SIDE SLOPES, PROVIDE A MINIMUM 8" HIGH MOUND OF EARTH MATERIAL AT THE TOP OF ALL SLOPES, MAINTAIN MOUND UNTIL VEGETATION IS COMPLETELY ESTABLISHED ON SIDE SLOPE THEN REMOVE/REGRADE TO A SMOOTH SURFACE CONSISTENT WITH ADJACENT GRADES TO ALLOW FOR POSITIVE DRAINAGE INTO THE POND OR CHANNEL AREAS. 10. PRIOR TO FINAL COMPLETION, STORM SEWER INLET IS TO BE CLEANED OF DEBRIS AND SEDIMENT.

SITE DESCRIPTION

GENERAL LOCATION & DESCRIPTION:

OWNER INFORMATION:

GULFTEX PROPERTIES, INC.
600 STAPLES, SUITE 205

CORPUS CHRISTI, TEXAS 78413
361-992-9700 EXT 16

PROJECT NAME: COLONY COMMERCIAL LOT 2, BLOCK 1 PHYSICIAN'S ER PROJECT LOCATION: APPROXIMATELY 1.68 ACRES LOCATED ADJACENT TO F.M. NO. 158 (BOONMILLE ROAD) ON THE NORTH SIDE. TO THE WEST LIES AUSTIN'S COLONY PKWY. THE SUBJECT TRACT ABUTS THE BRAZOS COUNTY BOONMILLE CEMETERY.

LATITUDE: 30°40'21.10"N LONGITUDE: 96°19'56.77"W

TOTAL SITE AREA IS: 1.68 ACRES
TOTAL AREA OF SITE EXPECTED TO BE DISTURBED: 0.99 ACRES


EXISTING SITE CONDITIONS:
LAND USE: VACANT
LAND COVER: GRASSED, SCATTERED TREES/BRUSH
AVERAGE GROUND SLOPE: 2.5%
SCS CURVE NUMBER: 84
RATIONAL 'C' FACTOR: 0.35
BECENAL WATERS: CARTER'S CREEK RECEIVING WATERS: CARTER'S CREEK SEGMENT NO. OF CLASSIFIED WATER BODY: 1209C

SOIL INFORMATION: BOOMVILLE FINE SANDY LOAM, 1 TO 3 PERCENT SLOPES (BOA- USDA SOIL SURVEY) HYDROLOGIC SOIL GROUP: C

POST DEVELOPED SITE CONDITIONS: LAND USE: COMMERCIAL PRIMARY STANDARD INDUSTRIAL CLASSIFICATION CODE (SIC): 1542 SECONDARY STANDARD INDUSTRIAL CLASSIFICATION CODE (SIC): 1623 SCS CURVE NUMBER: 96 RATIONAL 'C' FACTOR: 0.84

NATURE OF ACTIVITIES: CLEARING OF EXISTING TREES & BRUSH; STRIPPING OF TOPSOIL; SITE CUT/FILL OPERATIONS, CONSTRUCTION OF BUILDING W/ ASSOCIATED PARKING, UTILITIES, & DETENTION POND; REPLACEMENT OF TOPSOIL & REVEGETATION.

SEQUENCE OF MAJOR ACTIVITIES: 1. INSTALL SILT FENCE AT DOWNSTREAM LIMITS OF CONSTRUCTION & STOCK PILE AREAS
2. INSTALL ROCK CONSTRUCTION ENTRANCE
3. CLEAR SITE
4. EARTHWORK: SITE CUT/FILL, GRADING, UTILITY INSTALLATION, PAVING OPERATIONS
5. AFTER ESTABLISHMENT OF GRASS, REMOVE ALL TEMPORARY EROSION CONTROL
(SILT-FENCE); RE-SOD ALL AREAS NOT HAVING PERMANENT GRASS COVERAGE AS DEFINED.



1. GRAVEL FOR FILTER BAGS TO BE 3/4" GRAVEL. 2. FILTER BAGS TO BE PERVIOUS BURLAP BAGS OR SYNTHETIC NET BAGS (1/8" MESH) APPROX. 24" LONG, 12" WIDE AND 6" HIGH. 3. MAINTAIN FROM INSTALLATION OF INLET/DRIVEWAY THROUGH EACH STAGE OF ROADBED CONSTRUCTION (SUBGRADE, BASE, HMAC) UNTIL SUBSTANTIAL COMPLETION OF PROJECT.

4. CLEAN SEDIMENT ACCUMULATION AS REQUIRED ALLOWING NO MORE THAN 3" OF SEDIMENT BUILD—UP AROUND BAGS.

GRAVEL FILTER BAG

NOTES:

NOT TO SCALE


THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF ALFRED A. PAINE, P.E. 97221 ON 5/18/2016 FOR THE PURPOSE OF INTERIM REVIEW -NOT FOR CONSTRUCTION-

D U R D ENGINEERI TEXAS A XYAN, TEXA XYAN, 1879) 8 AX: (979) 8 GISTRATIO

D O d.b.a. (410

C2.

SHEET NO.




NOTES:
1. THE LENGTH OF THE TYPE 1 CONSTRUCTION EXIT SHALL BE 50' MIN. 2. THE COARSE AGGREGATE SHOULD BE OPEN GRADED WITH A SIZE OF 4" TO 8".

4. THE CONSTRUCTION EXIT FOUNDATION COURSE SHALL BE FLEXIBLE BASE, BITUMINOUS CONCRETE, PORTLAND CEMENT, OR OTHER MATERIAL AS APPROVED BY ENGINEER.

6. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.

TXDOT TYPE 1-CONSTRUCTION ENTRANCE/EXIT



1. ALL UTILITIES AND SERVICE LINES SHOWN ARE TAKEN FROM BEST AVAILABLE RECORD INFORMATION BASED ON CONSTRUCTION UTILITY MAP DOCUMENTS OBTAINED BY CIVIL ENGINEERING CONSULTANTS (CEC) FROM CITY & INDEPENDENT AGENCIES AND/OR ABOVE GROUND FIELD EVIDENCE. SHOWN POSITIONS MAY NOT REPRESENT AS—BUILT POSITIONS. CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONDITIONS PRIOR TO CONSTRUCTION OF WORK ELEMENT AFFECTED. OWNER AND ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF INFORMATION OR DATA RELIED ON TO DEPICT UNDERGROUND FACILITIES. CONTRACTOR IS TO CONTACT OWNERS OF ALL UTILITIES AND SERVICE LINES WITHIN THE PROJECT AREA AND NOTIFY OF INTENT AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS. CONTRACTOR IS TO VERIFY THE EXACT LOCATION AND VERTICAL POSITIONING OF ALL PIPELINES, EXISTING UTILITIES, AND SERVICE LINES WITHIN THE PROJECT AREA WHETHER SHOWN ON THE PLANS OR NOT, AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS AND ANY RELOCATION, REMOVAL, AND INSTALLATION, OR ADJUSTMENTS TO ALL EXISTING FACILITIES REQUIRED FOR PROSECUTION OF THE WORK. CONTRACTOR IS TO MAINTAIN STRUCTURAL INTEGRITY OF ALL PIPELINES, ELECTRIC TRANSMISSION POLES AND LINES, PERMANENT AND TEMPORARY UTILITIES. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DONE TO EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CONSTRUCTION ACTIVITIES.

CONTRACTOR TO CONTACT TEXAS811 & CITY OF BRYAN WATER SERVICES DEPARTMENT 96 HOURS PRIOR TO CONSTRUCTION. SPECIFIC ATTENTION SHOULD BE PAID TO FRANCHISE UTILITIES AS WELL AS OIL AND GAS PIPELINE COMPANIES, SHOULD A CONFLICT ARISE BETWEEN THE PROPOSED CONSTRUCTION AND AN EXISTING UTILITY, CONTACT CEC 48 HOURS PRIOR TO CONSTRUCTION.

2. CONTRACTOR IS TO MAINTAIN AND INSURE INTEGRITY OF ALL EXISTING UTILITIES. CLOSE ATTENTION IS TO BE PAID TO ANY EXISTING POWER, TELEPHONE, & FIBER OPTIC LINES & POLES.

3. UNLESS OTHERWISE DIRECTED BY THE OWNER, ALL MATERIALS AND DEBRIS DEMOLISHED OR REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN A MANNER SATISFACTORY TO THE OWNER & ENGINEER. 4. CONTRACTOR SHALL PREVENT TRANSPORT OF SEDIMENT TO ADJACENT PROPERTIES AND PUBLIC RIGHT OF WAYS AND IS RESPONSIBLE FOR CLEANUP IF SUCH OCCURS. CONTRACTOR IS TO INSURE NO CONSTRUCTION DEBRIS OR MUD IS TRACKED OR DISCARDED ON TO ANY PUBLIC OR PRIVATE STREETS OR LAND AND IS RESPONSIBLE FOR SITE CLEANUP AFTER EACH DAYS WORK. CONTRACTOR IS TO MAKE USE OF BEST MANAGEMENT PRACTICES TO PREVENT SEDIMENT FROM LEAVING THE SITE OR ENTERING EXISTING STORM SEWER OR CREEK AREAS. CONTRACTOR SHALL MAINTAIN EROSION CONTROL THROUGHOUT CONSTRUCTION PERIOD AND UNTIL GRASS IS ESTABLISHED.

5. CONTRACTOR IS TO BROADCAST SEED ALL DISTURBED AREAS FOR RE-ESTABLISHMENT OF VEGETATION WITH GRASS SEED MIX AS INDICATED IN THE SWP3 PLAN OR LANDSCAPE PLAN (DEPENDING ON LOCATION). CONTRACTOR TO DISK AREAS TO BE SEEDED TO A DEPTH OF 6". CONTRACTOR TO GUARANTEE COVERAGE AND ESTABLISHMENT OF GRASS FOR A PERIOD OF 6 MOS. COVERAGE SHALL BE DEFINED AS 95% OF THE PLANTED AREA WITH UNIFORM COVERAGE OF GRASS GREATER THAN 1" IN HEIGHT WITH NO BARE SPOTS GREATER THAN 2 SF.

6. LIMITS OF WORK: CONTRACTOR IS TO CONFINE ALL WORK TO OWNER'S PROPERTY. NO CONSTRUCTION ACTIVITY IS ALLOWED ON OR THROUGH PRIVATE PROPERTY UNLESS COVERED BY A PUBLIC UTILITY EASEMENT OR OTHER DOCUMENTED AGREEMENT. 7. CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTAINMENT AND PROPER DISPOSAL OF ALL LIQUID AND SOLID WASTE ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL USE ALL MEANS NECESSARY TO PREVENT THE OCCURRENCE OF WIND BLOWN LITTER FROM THE PROJECT SITE.

A GEOTECHNICAL INVESTIGATION OF THE SITE SURFICIAL & SUBSURFACE SOILS HAS BEEN CONDUCTED BY SAWMACK GEOTECHNICAL & TESTING, LLC ON MAY 4TH, 2016 (SAWMACK PROJECT NO. 16-159). TO ENSURE PROPER SUBGRADE PREPARATION, PRIOR TO CONSTRUCTION, IT IS RECOMMENDED THAT THE CONTRACTOR REVIEW THE GEOTECHNICAL REPORT AND ADHERE TO THE GEOTECHNICAL ENGINEER'S RECOMMENDATIONS REGARDING SUBGRADE SUITABILITY, STRENGTH, AND ANY NECESSARY STABILIZATION SHOULD BE OBTAINED IN A CERTIFIED

1. PRIOR TO PREPARATION OF SUBGRADE AND ANY FILL OPERATIONS, THE CONTRACTOR MUST CLEAR & GRUB OR OTHERWISE STRIP AREA OF TOP SOIL TO EXISTING, STABLE MATERIAL. SURFACES EXPOSED AFTER THE STRIPPING OF VEGETATION AND REMOVAL OR ANY SURFICIAL SOILS SHALL THEN BE PROOF ROLLED TO LOCATE UNSTABLE OR NON-UNIFORM AREAS. ROLLING EQUIPMENT SHALL CONSIST OF PNEUMATIC TIRED ROLLER WITH GROSS LOADING TO BE AS NECESSARY TO PRODUCE SURFACE LOADING OF 20 LBS/SQ IN. CONTRACTOR TO OVER EXCAVATE UNSTABLE OR NON-UNIFORM AREAS, REMOVING AND REPLACING MATERIAL WITH SELECT FILL MATERIAL COMPACTED TO 95% STD. PROCTOR (ASTM D-698) AT A MOISTURE CONTENT OF OPTIMUM TO +3% OF OPTIMUM. ONLY AS MUCH TOPSOIL AS IS REQUIRED TO PLACE IN RIGHT OF WAY OR OTHER DISTURBED AREAS OF THE SITE FILL IS TO BE STOCKPILED FOR USE IN FINISHED GRADING. REMAINDER OF TOP SOIL IS TO BE REMOVED & DISPOSED OF OFF SITE.

CHARACTERISTICS OF THE SUBGRADE LAYER SHOULD BE VERIFIED BY IN-PLACE DENSITY TESTS. THE TESTS SHOULD BE PERFORMED AT AN AVERAGE RATE OF ONE TEST FOR EVERY 2,000 SQUARE FEET OF BUILDING PAD SUBGRADE AREA AND EVERY 4,000 SQUARE FEET OF PAVING SUBGRADE AREA. 2. PRIOR TO PREPARATION OF SUBGRADE AND ANY FILL OPERATIONS, THE CONTRACTOR SHALL COORDINATE WITH TESTING LAB TO ENSURE ALL TOPSOIL AND UNUSABLE MATERIAL HAS BEEN REMOVED.

3. FILL TO BE FROM SITE OBTAINED DETENTION/BORROW AREA AND TO BE COMPACTED TO 95% OF THE MAXIMUM DENSITY AS DETERMINED BY ASTM D-698 AT A MOISTURE CONTENT OF OPTIMUM TO +3% OF OPTIMUM. FILL TO BE PLACED IN 6" LIFTS. 4. TOPSOIL SHALL BE STOCKPILED ONLY AS NECESSARY FOR REPLACEMENT IN NON PAVED AREAS. MAXIMUM HEIGHT SHALL NOT EXCEED 10', AND THE SIDE SLOPE SHALL NOT BE STEEPER THAN 3:1. EXCESS TOPSOIL IS TO BE HAULED OFF SITE AND DISPOSED OF BY THE CONTRACTOR.

5. SUB-grade: Final compaction of the sub-grade to be 98% of the maximum density of the mixture as determined by astm d-698 at a moisture content between optimum to +3% of optimum.

THE OWNER SHALL OBTAIN AN INDEPENDENT TESTING LABORATORY TO CONDUCT ALL MATERIALS/COMPACTION TESTING. CONTRACTOR IS RESPONSIBLE TO NOTIFY AND COORDINATE WITH LABORATORY IN ADVANCE OF WHEN OPERATIONS WILL BE PERFORMED. INITIAL TESTING SHALL BE PAID FOR BY THE OWNER. FAILED TESTS AND RE-TESTS SHALL BE PAID FOR BY THE CONTRACTOR. WORK WILL NOT BE ACCEPTABLE FOR PAYMENT WITHOUT PASSED TEST RESULTS. COPIES OF RESULTS TO BE DELIVERED TO OWNER AND CEC. SUB-GRADE MATERIAL: OPTIMUM MOISTURE/DENSITY RELATIONSHIP TO BE DETERMINED AT RATE OF ONE SAMPLE PER MATERIAL ENCOUNTERED. IN PLACE DENSITY & MOISTURE CONTENT TESTS TO BE TAKEN AT A RATE OF 1(MINIMUM) FOR EVERY 250 SY FOR

7. FINISHED GRADING: SPREAD AT LEAST 6" OF TOP SOIL, DISK AND HYDROMULCH FOR PERMANENT VEGETATION AFTER ACHIEVING FINISHED PLAN GRADES IN FILL AREA. FINISHED GRADE IN EXCAVATION AREA TO BE PER PLAN GRADES AFTER APPLICATION OF TOPSOIL. CONTRACTOR TO GRADE BACK TO EXISTING GROUND AT PROPERTY LIMITS UNLESS OTHERWISE NOTED.

1. CONCRETE SHALL BE 3500 PSI, 28 DAY COMPRESSIVE STRENGTH PORTLAND CEMENT CONCRETE. TEST CYLINDERS SHALL BE TAKEN 1 SET OF 3 PER 100 CY OF CONCRETE PLACED OR A MINIMUM OF 1 SET OF 3 PER STRUCTURE AT TIME OF POUR. 2. STEEL REINFORCEMENT FOR USE IN THE RIGID PAVEMENT SYSTEM SHALL BE GRADE 60 OR BETTER. THE CONCRETE SHALL BE PLACED ON A EIGHT INCH CHEMICALLY TREATED STABILIZED SUBGRADE. SUBGRADE FILL TO BE COMPACTED TO 95% OF THE MAXIMUM DENSITY AS DETERMINED BY ASTM D-698 AT A MOISTURE CONTENT OF OPTIMUM TO +4% OF OPTIMUM.

3. JOINTING: FOR THE CONCRETE SIDEWALKS AND DRIVES, FREQUENT CONTROL JOINTS SHOULD BE USED TO DIRECT SHRINKAGE CRACKING WITH A MAXIMUM JOINT SPACING AS SHOWN: 4" THICK SIDEWALK - SIDEWALK WIDTH EXPANSION JOINTS SHALL BE PLACED AT ANTICIPATED STRESS POINTS AND DOWELS SHALL BE PLACED ACROSS THESE JOINTS.

4. CONTRACTOR SHALL EXCLUDE TRAFFIC FROM CONCRETE PAVEMENT BY MEANS OF BARRICADES AND SIGNS UNTIL CONCRETE IS AT LEAST 14 DAYS OLD. CONSTRUCTION TRAFFIC SHALL BE EXCLUDED UNTIL CONCRETE HAS REACHED DESIGN STRENGTH. 5. MATERIAL AND METHODS FOR PAVEMENT MARKINGS SHALL CONFORM TO ITEM 666 OF THE TXDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES, WITH THE FOLLOWING EXCEPTIONS: 1) TYPE II MARKING MATERIALS NEED NOT BE PURCHASED FROM THE

CONSTRUCTION TESTING RECOMMENDATIONS: 1. THE OWNER SHALL OBTAIN AN INDEPENDENT TESTING LABORATORY TO CONDUCT ALL MATERIALS/COMPACTION TESTING. CONTRACTOR IS RESPONSIBLE TO NOTIFY AND COORDINATE WITH LABORATORY IN ADVANCE OF WHEN OPERATIONS WILL BE PERFORMED. INITIAL TESTING SHALL BE PAID FOR BY THE OWNER, FAILED TESTS AND RE-TESTS SHALL BE PAID FOR BY THE CONTRACTOR. WORK WILL NOT BE ACCEPTABLE FOR PAYMENT WITHOUT PASSED TEST RESULTS. COPIES OF RESULTS TO BE DELIVERED TO OWNER AND CMIL ENGINEERING CONSULTANTS.

2. SUB-GRADE MATERIAL / GENERAL FILL: OPTIMUM MOISTURE/DENSITY RELATIONSHIP TO BE DETERMINED AT RATE OF ONE SAMPLE PER MATERIAL ENCOUNTERED. IN-PLACE DENSITY & MOISTURE CONTENT TESTS TO BE TAKEN AT A RATE OF 1 (MINIMUM) FOR EVERY 250 SY FOR EACH 6" OF COMPACTED THICKNESS. 3. SUBGRADE STABILIZATION: A LIME OR CEMENT SERIES SHALL BE RUN TO DETERMINE THE EXACT AMOUNT OF LIME OR CEMENT TO BE ADDED TO THE SUBGRADE PRIOR TO COMMENCEMENT OF STABILIZATION. IN-PLACE DENSITY & MOISTURE CONTENT TESTS TO BE TAKEN AT A RATE OF 1(MINIMUM) FOR EVERY 250 SY FOR EACH 6" OF COMPACTED THICKNESS.

LEGEND

EXISTING EDGE OF PAVEMENT PROPOSED EDGE OF PAVEMENT EXISTING CONTOURS PROPOSED CONTOURS EXISTING SANITARY SEWER MANHOLE EXISTING SANITARY SEWER LINE EXISTING STORM SEWER MANHOLE EXISTING STORM SEWER LINE

EXISTING TELEPHONE PEDESTAL EXISTING TELEPHONE LINE EXISTING TELEVISION PEDESTAL EXISTING TELEVISION CABLE EXISTING WATER METER EXISTING WATER LINE EXISTING WATER VALVE

EXISTING FIRE HYDRANT EXISTING OVERHEAD ELECT. LINE EXISTING POWER POLE EXISTING LIGHT POLE

EXISTING PIPE LINE

PR. EL = PROPOSED ELEVATION EX. EL = EXISTING ELEVATIONGF = GUTTER FLOW LINE BC = BACK OF CURB TP = TOP OF PAVEMENT


TS = TOP OF SIDEWALK


300 ----ST----______T____ D U R D
ENGINEER
TEXAS /
YAN, TEX,
YAN, TEX,
SEL: (979) &
AX: (979) &
GISTRATIC ΙΙΘ̈́ΙΙ 0 a C

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF ALFRED A. PAINE, P.E. 97221 ON 5/18/2016 FOR THE PURPOSE OF INTERIM REVIEW. -NOT FOR CONSTRUCTION-


 $\mathbf{\Omega}$


C3.1







ADA RAMP DETAIL







CONCRETE PAVEMENT JUNCTION AT EXISTING HMAC PAVEMENT




NOT TO SCALE


NOTE:

1. EXPANSION JOINTS IN CURB & GUTTER SHALL BE SPACED AT A MAXIMUM DISTANCE OF 50' APART AND AT ALL RADIUS POINTS, P.T.'S AND P.C.'S.

2. SLOPE GUTTER PER GRADING PLAN TO ENSURE POSITIVE DRAINAGE

MONOLITHIC CONCRETE CURB & GUTTER SECTION





NOT TO SCALE

SMOOTH BAR DOWEL

1/2"x7" • 18" O.C.

(DOWEL TO BE OILED

W/ STD. NO. 40 SAE

GRADE)

CURB AS PER

STD. DTL.

T/2" EXPANSION JOINT
TOOLED 1/8" RAD. ALL

EXPANSION CAP

PAVEMENT JUNCTION / PAVMENT REPAIR

THREADED CAP

TEXAS MU.T.C.D.


R7-8 & R7-8A

AS APPLICABLE

VAN ACCESSIBLE

2"GALVANIZED
STEEL PIPE SET
IN 8" DIA X 2'-0"
DEEP CONC.


HANDICAP PARKING SIGN



NOTE:

1. EXPANSION JOINTS IN CURB SHALL BE
SPACED AT A MAXIMUM DISTANCE OF 50' APART
AND AT ALL RADIUS POINTS, P.T.'S AND P.C.'S.

CONCRETE FLUSH CURB SECTION



1. EXPANSION JOINTS IN CURB & GUTTER SHALL BE SPACED AT A MAXIMUM DISTANCE OF 50' APART AND AT ALL RADIUS POINTS, P.T.'S AND P.C.'S.

2. SLOPE GUTTER PER GRADING PLAN TO ENSURE POSITIVE DRAINAGE

MONOLITHIC CONCRETE SPILL CURB SECTION

NOT TO SCALE

SULTANTS
UITE A

2
APPROVED: AAP
JOB NO: E0649900

DONDURDEN, INC d.b.a. CIVIL ENGINEERING CONSULTANT 4101 S. TEXAS AVE, SUITE A BRYAN, TEXAS 77802 TEL: (979) 846-6212 FAX: (979) 846-8252 REGISTRATION #F-2214

SAN ANTONIO / LAREDO BRYAN / COLLEGE STATION

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF ALFRED A. PAINE, P.E. 97221 ON 5/18/2016 FOR THE PURPOSE OF INTERIM REVIEW.

-NOT FOR CONSTRUCTION—

REV DATE DESCRIPTION

L-2 B-1 PHYSICIANS ER

GULFTEX PROPER
ONY COMMERCIAL L-2
NOTES & DE

C5.1