


CLIENT	BRYAN I.S.D.	
PROJECT NUMBER	15-1097	
DATE	07-14-2016	
DRAWN BY	PR	
CHECKED BY	ASP	
REVISIONS	No.	Description

NOT FOR CONSTRUCTION

SITE PLAN

CAUTION: CONTACT THE TEXAS EXCAVATION SAFETY SYSTEM (DIG-TESS) AT 1-800-344-8377 TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



PROJECT BENCHMARKS:
SQUARE CUT ELEVATION = 297.044'
SQUARE CUT ELEVATION = 291.682'

GESSNER ENGINEERING
GESSNER ENGINEERING
Corporate Office
2501 Ashford Drive
College Station, Texas 77840
www.gessnerengineering.com

FIRM REGISTRATION NUMBER:
TYPE F-7461,
TPLSF-10193910


SITE PLAN FOR:
MITCHELL ELEMENTARY SCHOOL
2500 AUSTINS COLONY PARKWAY
BRYAN, TEXAS 77808

LEGAL DESCRIPTION:
JOHN AUSTIN, BLOCK 19, LOT 10
ACRES 10.54, MITCHELL SCHOOL

ZONING:
RESIDENTIAL, RD-7

OWNER:
BRYAN I.S.D.
101 NORTH TEXAS AVENUE
BRYAN, TX 77803
TELEPHONE: 979-209-7062
CONTACT: JEFF WINDSOR
EMAIL: JEFF.WINDSOR@BRYANISD.ORG

VICINITY MAP




SITE PLAN NOTES:

- CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN THESE PLANS AND ON-SITE FIELD CONDITIONS OR SPECIFICATIONS OF OTHER DISCIPLINES.
- THE CONTRACTOR IS REQUIRED TO OBTAIN ALL NECESSARY PERMITS, AS WELL AS INSPECTION APPROVALS.
- A COPY OF APPROVED CONSTRUCTION PLANS SHALL BE KEPT ON SITE AT ALL TIMES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL MAINTAIN A SET OF REDLINE DRAWINGS TO RECORD AS-BUILT CONDITIONS.
- REFER TO ARCHITECTURAL PLANS FOR COMPLETE BUILDING DIMENSIONS.
- REFER ARCHITECTURAL PLANS FOR PROPOSED SITE SIGNAGE AS APPLICABLE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTAINMENT AND PROPER DISPOSAL OF ALL LIQUID AND SOLID WASTE ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL USE ALL MEANS NECESSARY TO PREVENT THE OCCURRENCE OF WIND BLOWN LITTER FROM THE PROJECT SITE.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AN ORDERLY PROJECT SITE. THE CONTRACTOR SHALL CLEAN AND REMOVE ANY SURPLUS OR DISCARDED MATERIALS, TEMPORARY STRUCTURES, AND DEBRIS FROM THE PROJECT SITE.
- THE CONTRACTOR IS RESPONSIBLE FOR STORAGE AND SAFE-GUARDING OF ALL MATERIALS AND EQUIPMENT AT THE PROJECT SITE TO MAINTAIN A SAFE AND SECURE PROJECT.
- THE CONTRACTOR SHALL COORDINATE SITE STORAGE WITH THE OWNER TO NOT OBSTRUCT DRIVES, ACCESS, OR OTHER OPERATIONAL REQUIREMENTS.
- ANY ADJACENT RIGHT-OF-WAY (R.O.W.) OR PROPERTY AFFECTED DURING CONSTRUCTION, SHALL BE RETURNED TO PRE-CONSTRUCTION CONDITION AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL PROTECT ALL SURVEY MONUMENTATION, BENCHMARKS, AND MARKERS DURING CONSTRUCTION.
- THE CONTRACTOR MUST PROVIDE CONSTRUCTION STAKING SERVICES BASED ON THE INFORMATION PROVIDED IN THE PLANS.
- IRRIGATION SYSTEM WILL BE PROTECTED BY EITHER A PRESSURE VACUUM BREAKER, A REDUCED PRESSURE PRINCIPLE BACK FLOW DEVICE, OR A DOUBLE-CHECK BACK FLOW DEVICE, AND INSTALLED AS PER CITY ORDINANCE 2394.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES OR SERVICE LINES DURING THE CONSTRUCTION PROCESS. WHERE EXISTING UTILITIES OR SERVICE LINES ARE DAMAGED, THE CONTRACTOR SHALL REPAIR OR REPLACE THE UTILITY OR SERVICE LINE WITH THE SAME TYPE OF MATERIAL AND CONSTRUCTION, OR BETTER. ALL MATERIAL AND LABOR SHALL BE AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL STATE AND FEDERAL REGULATIONS REGARDING CONSTRUCTION ACTIVITIES NEAR ENERGIZED OVERHEAD ELECTRIC LINES.
- THE CONTRACTOR ACKNOWLEDGES THAT THE LOCATION AND/OR ELEVATION OF THE EXISTING UTILITIES SHOWN ON THE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, CITY MAPS AND, WHEN POSSIBLE, FIELD MEASUREMENTS. THE INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE.
- THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE UTILITY COMPANY 48 HOURS PRIOR TO EXCAVATION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS.
- ALL BACK FLOW DEVICES WILL BE INSTALLED AND TESTED UPON INSTALLATION AS PER CITY ORDINANCE 2394.
- ALL WATER LINES TO BE CL 305 DR 14 PVC, MEETING AWWA C-900 OR C-909 STANDARDS.
- SANITARY SEWER LINES TO BE SDR-26 PVC.
- SANITARY SEWER LINES SHALL BE CONSTRUCTED IN ACCORDANCE WITH TCEQ REQUIREMENTS FOR SEPARATION AND CROSSINGS, AND IN ACCORDANCE WITH THE 2012 INTERNATIONAL PLUMBING CODE.
- ALL METERS TO BE LOCATED WITHIN THE P.U.E.

EROSION CONTROL NOTES:

- THE CONTRACTOR SHALL PROVIDE EROSION PROTECTION AT ALL LOCATIONS OF CONSTRUCTION.
- THE CONTRACTOR WILL REMOVE ALL EXCESS SOIL FROM CONSTRUCTION VEHICLES PRIOR TO EXITING THE SITE.
- THE CONTRACTOR SHALL UNDERTAKE PROPER METHODS TO REDUCE DUST GENERATION FROM THE SITE.
- THE CONTRACTOR MUST COMPLY WITH FEDERAL, STATE, AND LOCAL REGULATIONS REGARDING SEDIMENTS AND EROSION CONTROL.
- A COPY OF THIS PLAN MUST BE KEPT AT THE CONSTRUCTION FACILITY DURING THE ENTIRE CONSTRUCTION PERIOD.
- ALL FINISHED GRADES ARE TO BE HYDRO-MULCHED, SPOT SODDED OR SEEDED AND WATERED UNTIL GROWTH IS ESTABLISHED.

BUILDING DATA SUMMARY			
EXISTING USE:	MITCHELL ELEMENTARY SCHOOL		
PROPOSED USE:	ELEMENTARY SCHOOL ADDITIONS		
NO. OF STORIES:	1		
PROPOSED BUILDING:	TOTAL SF	HEIGHT (FT)	TYPE
	5,098	14	IIB
BUILDING SPRINKLER:	YES		
FIRM MAP NO.:	4804C0215F (Partially located in 100 year floodplain or floodway)		
PARKING TABULATION			
PARKING REQUIREMENT:	1/15 STUDENTS		
TOTAL PARKING REQUIRED:	560 STUDENTS/16=38 SPACES		
TOTAL PARKING PROVIDED:	88 SPACES (62 STD, 6 HC)		



NOTICE:
ENSURE CONTRACTOR GETS UTILITIES LOCATED AT THE TIME OF CONSTRUCTION DUE TO CLOSE PROXIMITY OF EXISTING 8" WATERLINE TO THE FIRE LANE EXTENSION.

