

## Capital Improvement Program Project: SW\_17\_006

Funded	Original Cost Year:	2017
	Projected Cost:	\$741,000
Wayside Drive.	Projected Cost Year:	2022
Culpepper Manor Subdivision: Behind 1917 S Texas Avenue near the intersection of Vinewood Drive and	CIP Ranking:	19
	Type / Source:	Storm Water
	Council District:	4
Wayside Drainage Improvements Ph 2	CIP Project:	TBD
	Culpepper Manor Subdivision: Behind 1917 S Texas Avenue near the intersection of Vinewood Drive and Wayside Drive.	Culpepper Manor Subdivision: Behind 1917 S Texas Avenue near the intersection of Vinewood Drive and Wayside Drive. Council District: Type / Source: CIP Ranking: Projected Cost Year: Projected Cost:

This project would replace and an existing storm sewer system in the Culpepper Manor Subdivision that is near the intersection of Vinewood Drive and Wayside Drive. The existing 18", 24", 30" and 36" storm sewer would be replaced with 30" storm sewer and 3'x4' box culverts, inlets and junction boxes.

## **Justification**

Miscellaneous improvements to the stormdrain system to enhance stormwater conveyance from Wayside to the creek. The existing system is undersized and excess flows travel through private property as it makes it's way to the creek. Numerous complaints have been received in the area which also includes repetitive loss properties.

			Funding				
Туре	<u>Original</u>	<u>Source</u>	<u>2018</u>	<u>2019</u>	<u>2020</u>	<u>2021</u>	2022
Drainage	\$88,500	Bonds	\$0	\$0	\$0	\$0	\$108,000
Design/Survey	\$88,500		\$0	\$0	\$0	\$0	<b>\$108,000</b>
Drainage	\$520,000	Bonds	\$0	\$0	\$0	\$0	\$633,000
Const/ROW	\$520,000		\$0	\$0	\$0	\$0	\$633,000
Total	\$608,500		\$0	\$0	\$0	\$0	\$741,000



Funding Source Summary								
Source	<u>Original</u>		<u>2018</u>	<u>2019</u>	<u>2020</u>	<u>2021</u>	<u>2022</u>	
Bonds	\$608,500		\$0	\$0	\$0	\$0	\$741,000	
Total	\$608,500		\$0	\$0	\$0	\$0	\$741,000	



