VICINITY MAP

SITE PLAN FOR:
HENDERSON ELEMENTARY SCHOOL
801 MATOUS DRIVE
BRYAN, TX 77802

LEGAL DESCRIPTION:
ZENO PHILLIPS, BLOCK 7, LOT 20 (TR-285),
ACRES 10.88, HENDERSON SCHOOL

ZONING:
RESIDENTIAL, R-7

OWNER:
BRYAN I.S.D.
101 NORTH TEXAS AVENUE
BRYAN, TX 77803
TELEPHONE: 979-209-7062
CONTACT: JEFF WINDSOR
EMAIL: JEFF.WINDSOR@BRYANISD.ORG

BUILDING DATA SUMMARY			
EXISTING USE:	HENDERSON ELEMENTARY SCHOOL		
PROPOSED USE:	ELEMENTARY SCHOOL ADDITIONS		
NO. OF STORIES:	1		
PROPOSED BUILDING:	TOTAL SF	HEIGHT (FT)	TYPE
	13,705	15'-4"	IIB
	2,425	15'-4"	IIB
BUILDING SPRINKLER SYSTEM:	YES		
FIRM MAP NO:	48041C0215F		

CAUTION: CONTACT THE TEXAS EXCAVATION SAFETY SYSTEM (DIG-TESS) AT 1-800-344-8377 TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.

N

0 40 80 120
SCALE: 1"= 40'

PROJECT BENCHMARK: ⊕BM

RAIL SPIKE IN POWER POLE
ELEVATION = 312.58'

SQUARE IN BACK OF CURB
ELEVATION = 319.25'

LEGEND

	PROPOSED BUILDING
	PROPOSED CONCRETE PAVEMENT
	PROPERTY LINE
	ADJACENT PROPERTY LINE
	BUILDING SETBACK LINE
	EXISTING PAVEMENT EDGE
	FIRELANE (RED CURB WITH 4" WHITE LETTERS: "FIRELANE NO PARKING TOW-AWAY ZONE")
340	EXISTING MAJOR CONTOURS
341	EXISTING MINOR CONTOURS
340	PROPOSED MAJOR CONTOURS
341	PROPOSED MINOR CONTOURS
W	EXISTING WATER LINE
	PROPOSED WATER LINE
SS	EXISTING SANITARY SEWER
	PROPOSED SANITARY SEWER
	EXISTING MANHOLE
FH	EXISTING FIRE HYDRANT
	PROPOSED HANDICAP PARKING
	PROPOSED WATER VALVE
	PROPOSED WATER METER
	PROPOSED SANITARY SEWER CLEANOUT
	PROPOSED SS DOUBLE CLEANOUT
FDC	PROPOSED FIRE DEPT. CONNECTION

SITE PLAN NOTES:

1. CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN THESE PLANS AND ONSITE FIELD CONDITIONS OR SPECIFICATIONS OF OTHER DISCIPLINES
2. THE CONTRACTOR IS REQUIRED TO OBTAIN ALL NECESSARY PERMITS, AS WELL AS INSPECTION APPROVALS.
3. A COPY OF APPROVED CONSTRUCTION PLANS SHALL BE KEPT ON SITE AT ALL TIMES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL MAINTAIN A SET OF REDLINE DRAWINGS TO RECORD AS-BUILT CONDITIONS.
4. REFER TO ARCHITECTURAL PLANS FOR COMPLETE BUILDING DIMENSIONS.
5. REF. ARCHITECTURAL PLANS FOR PROPOSED SITE SIGNAGE AS APPLICABLE.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTAINMENT AND PROPER DISPOSAL OF ALL LIQUID AND SOLID WASTE ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL USE ALL MEANS NECESSARY TO PREVENT THE OCCURRENCE OF WIND BLOWN LITTER FROM THE PROJECT SITE.
7. DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AN ORDERLY PROJECT SITE. THE CONTRACTOR SHALL CLEAN AND REMOVE ANY SURPLUS OR DISCARDED MATERIALS, TEMPORARY STRUCTURES, AND DEBRIS FROM THE PROJECT SITE.
8. THE CONTRACTOR IS RESPONSIBLE FOR STORAGE AND SAFE-GUARDING OF ALL MATERIALS AND EQUIPMENT AT THE PROJECT SITE TO MAINTAIN A SAFE AND SECURE PROJECT.
9. THE CONTRACTOR SHALL COORDINATE SITE STORAGE WITH THE OWNER TO NOT OBSTRUCT DRIVES, ACCESS, OR OTHER OPERATIONAL REQUIREMENTS.
10. ANY ADJACENT RIGHT-OF-WAY (R.O.W.) OR PROPERTY AFFECTED DURING CONSTRUCTION, SHALL BE RETURNED TO PRE-CONSTRUCTION CONDITION AT THE CONTRACTOR'S EXPENSE.
11. THE CONTRACTOR SHALL PROTECT ALL SURVEY MONUMENTATION, BENCHMARKS, AND MARKERS DURING CONSTRUCTION.
12. THE CONTRACTOR MUST PROVIDE CONSTRUCTION STAKING SERVICES BASED ON THE INFORMATION PROVIDED IN THE PLANS.
13. IRRIGATION SYSTEM WILL BE PROTECTED BY EITHER A PRESSURE VACUUM BREAKER, A REDUCED PRESSURE PRINCIPLE BACK FLOW DEVICE, OR A DOUBLE-CHECK BACK FLOW DEVICE, AND INSTALLED AS PER CITY ORDINANCE 2394.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES OR SERVICE LINES DURING THE CONSTRUCTION PROCESS. WHERE EXISTING UTILITIES OR SERVICE LINES ARE DAMAGED, THE CONTRACTOR SHALL REPAIR OR REPLACE THE UTILITY OR SERVICE LINE WITH THE SAME TYPE OF MATERIAL AND CONSTRUCTION, OR BETTER. ALL MATERIAL AND LABOR SHALL BE AT THE CONTRACTOR'S EXPENSE.
15. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL STATE AND FEDERAL REGULATIONS REGARDING CONSTRUCTION ACTIVITIES NEAR ENERGIZED OVERHEAD ELECTRIC LINES.
16. THE CONTRACTOR ACKNOWLEDGES THAT THE LOCATION AND/OR ELEVATION OF THE EXISTING UTILITIES SHOWN ON THE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, CITY MAPS AND, WHEN POSSIBLE, FIELD MEASUREMENTS. THE INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE.
17. THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE UTILITY COMPANY 48 HOURS PRIOR TO EXCAVATION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS.
18. ALL BACK FLOW DEVICES WILL BE INSTALLED AND TESTED UPON INSTALLATION AS PER CITY ORDINANCE 2394.
19. ALL WATER LINES TO BE CL 235 DR 14 PVC, MEETING AWWA C-900 OR C-909 STANDARDS .
20. ALL SANITARY SEWER LINES TO BE SDR-26 PVC.
21. SANITARY SEWER LINES SHALL BE CONSTRUCTED IN ACCORDANCE WITH TCEQ REQUIREMENTS FOR SEPARATION AND CROSSINGS, AND IN ACCORDANCE WITH THE 2012 INTERNATIONAL PLUMBING CODE.
22. ALL METERS TO BE LOCATED WITHIN THE P.U.E.

Stantec
2338 COOLIDGE
SUITE 100
BERKLEY, MICHIGAN 48072
P 248.336.4700
F 248.336.4701

GESSNER
ENGINEERING
GESSNER ENGINEERING
Corporate Office
2501 Ashford Drive
College Station, Texas 77840
www.gessnerengineering.com
FIRM REGISTRATION NUMBER:
TBPE F-7451,
TBPLSF-10193910

STATE OF TEXAS
ALEX JUNG-PETERKORN
12594
LICENSED
PROFESSIONAL ENGINEER
PRELIMINARY

BRYAN INDEPENDENT SCHOOL DISTRICT

HENDERSON
ELEMENTARY SCHOOL
ADDITION
BRYAN, TEXAS

DRAWN: ASP
CHECKED: JNP

ISSUE:

SHEET TITLE:
SITE PLAN

C100

Project #: 15-0319

11/5/2015
C100 SITE PLAN.dwg