






ORIGINAL PLAT
(365/397)



REPLAT



General Notes:

- The purpose of this plat is to shift the property line separating the two lots.
- Bearing system shown hereon is based on the Texas Coordinate System of 1983, central zone (4203), grid North as established from GPS observation using the Leica Smartnet NAD83 (NA2011) EPOCH 2010 multi-year CORS Solution 2 (MYCS2).
- Said lots are not under the 100 year flood plain, as identified by the Federal Emergency Management Agency on Community Panel No. 48041C0215F Dated: 4/2/2014.
- 5/8" Iron rods with plastic cap stamped "Carломagno - RPLS 1562" will be set at all angle points and lot corners unless otherwise stated.
- The topography shown is based on survey data.
- All minimum building setbacks shall be in accordance with the City of Bryan Code of Ordinances.
- This property is zoned Residential Neighborhood Conservation (R-NC).
- Where electric facilities are installed, the BTU has the right to install, operate, relocate, construct, reconstruct, add to, maintain, inspect, patrol, enlarge, repair, remove and replace said facilities upon, over, under, and across the property included in the PUE, and the right of ingress and egress on property adjacent to the PUE to access electric facilities.

Annotations:

ROW-	Right-of-Way
HMAC-	Hot mix Asphaltic concrete
DRBCT-	Deed Records of Brazos County, Texas
ORBCT-	Official Records of Brazos County, Texas
OPBCT-	Official Public Records of Brazos County, Texas
(-)	Record information
(CM)-	Controlling Monument used to establish property boundaries
PUE-	Public Utility Easement
CAE-	Cross Access Easement
PAE-	Public Access Easement
DE-	Drainage Easement
PrDE-	Private Drainage Easement
TYP-	Typical
N/F-	Now or Formerly

CERTIFICATE OF OWNERSHIP AND DEDICATION

STATE OF TEXAS
COUNTY OF BRAZOS

I, Nikolas Bogost, owner and developer of the land shown on this plat, being the tract of land as conveyed to me in Deeds of Records of Brazos County in Volume 365, Page 397, and whose name is subscribed hereto, hereby dedicates to the use of the public forever all streets, alleys, parks, greenways, infrastructure, easements, and public places thereon shown for the purpose identified.

Nikolas Bogost

CERTIFICATE OF OWNERSHIP AND DEDICATION

STATE OF TEXAS
COUNTY OF BRAZOS

We, Stephen O. Babalola and Abimbola Babalola, owners and developers of the land shown on this plat, being the tract of land as conveyed to us, in Deeds of Records of Brazos County in Volume 365, Page 397, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, greenways, infrastructure, easements, and public places thereon shown for the purpose identified.

Stephen O. Babalola Abimbola Babalola

CERTIFICATE OF THE SURVEYOR

STATE OF TEXAS
COUNTY OF BRAZOS

I, Dante Carlomagno, Registered Professional Land Surveyor No. 1562, in the State of Texas, hereby certify that this plat is true and correct and was prepared from an actual survey of the property and that property markers and monuments were placed under my supervision on the ground, and that the metes and bounds describing said subdivision will describe a closed geometric form.

Dante Carlomagno, R.P.L.S. No. 1562

APPROVAL OF THE CITY PLANNER

I, _____, the undersigned, City Planner and/or designated Secretary of the Planning and Zoning Commission of the City of Bryan, hereby certify that this plat is in compliance with the appropriate codes and ordinances of the City of Bryan and was approved on the _____ day of _____, 20____.

City Planner
Bryan, Texas

APPROVAL OF THE CITY ENGINEER

I, _____, the undersigned, City Engineer of the City of Bryan, hereby certify that this plat is in compliance with the appropriate codes and ordinances of the City of Bryan and was approved on the _____ day of _____, 20____.

City Engineer, Bryan, Texas

CERTIFICATE OF THE COUNTY CLERK

STATE OF TEXAS
COUNTY OF BRAZOS

I, _____, County Clerk in and for said County, do hereby certify this plat together with its certificate of authentication was filed for record in my office the _____ day of _____, 20____, in the Official Records of Brazos County in Volume _____, Page _____.

County Clerk, Brazos County, Texas

METES AND BOUNDS DESCRIPTION OF A 0.55 ACRES TRACT OUT OF THE JOHN AUSTIN SURVEY, A-2, BRAZOS COUNTY, TEXAS

BEING A TRACT OF LAND CONTAINING 0.55 ACRES, OUT OF THE JOHN AUSTIN SURVEY, A-2, LOCATED IN BRAZOS COUNTY, TEXAS, ALSO BEING ALL OF LOT 1 (LOT 1) AND LOT 2 (LOT 2), BLOCK 17, OUT OF THE MEMORIAL FOREST IV SUBDIVISION (MEMORIAL FOREST SUB.), PHASE 2, AS RECORDED IN VOLUME 355, PAGE 397 OF THE DEED RECORDS OF BRAZOS COUNTY, THE SAID 0.55 ACRES TRACT BEING THE SAME TRACT OF LAND AS SHOWN ON THE PLAT OF SURVEY PREPARED BY CARLOMAGNO SURVEYING, INC., HAVING THE FILE NAME 25063.DWG AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS, WITH ALL CONTROL REFERENCED TO THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, NAD83:

COMMENCING AT A BRASS DISK SET IN CONCRETE MARKED "CITY OF BRYAN GPS-35" FOUND FOR A POINT WITHIN THE JOHN AUSTIN SURVEY, A-2, ALSO BEING A POINT WITHIN THE CITY LIMITS OF BRYAN, TEXAS, HAVING THE TEXAS COORDINATE VALUE OF X= 10,230,985.49 AND Y= 3,545,537.09;

THENCE CROSSING THE SAID JOHN AUSTIN SURVEY, A-2, SOUTH 47°53'38" EAST, A DISTANCE OF 4,955.05 FEET TO A 5/8" IRON ROD WITH AN ORANGE PLASTIC CAP MARKED "CARLOMAGNO RPLS 1562" SET FOR THE PLACE OF BEGINNING OF THIS TRACT, ALSO BEING THE WEST CORNER OF THIS TRACT, ALSO BEING THE WEST CORNER OF THE SAID LOT 1, ALSO BEING A POINT ALONG THE EAST RIGHT-OF-WAY LINE OF VILLA MARIA ROAD (VILLA MARIA RD.), A CALLED 100 FOOT RIGHT-OF-WAY, ALSO BEING THE SOUTH CORNER OF KEYSTONE SUBDIVISION (KEYSTONE SUB.), A SUBDIVISION RECORDED VOLUME 2195, PAGE 301 OF THE D.R.B.C., HAVING THE TEXAS COORDINATE VALUE OF X= 10,227,663.10 AND Y= 3,549,213.26;

THENCE ALONG THE COMMON LINE OF THIS TRACT AND THE SAID KEYSTONE SUB., NORTH 73°59'16" EAST, A DISTANCE OF 73.81 FEET TO A 5/8" IRON ROD WITH AN ORANGE PLASTIC CAP MARKED "CARLOMAGNO RPLS 1562" SET FOR A NORTHWEST ANGLE POINT OF THIS TRACT, ALSO BEING A POINT ALONG THE NORTHWEST BOUNDARY LINE OF THE SAID LOT 1, ALSO BEING A POINT ALONG THE SOUTHWEST BOUNDARY LINE OF THE SAID KEYSTONE SUB., FROM WHICH A 1/2" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "TSL 6410" FOUND FOR REFERENCE BEARS: NORTH 74°18'59" EAST, A DISTANCE OF 10.92 FEET;

THENCE ALONG THE COMMON LINE OF THIS TRACT AND THE SAID KEYSTONE SUB., NORTH 74°18'59" EAST, A DISTANCE OF 90.98 FEET TO A 1/2" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "TSL 6410" FOUND FOR THE NORTH CORNER OF THIS LOT, ALSO BEING THE NORTH CORNER OF THE SAID LOT 2, ALSO BEING A POINT ALONG THE SOUTHWEST BOUNDARY LINE OF THE SAID KEYSTONE SUB., ALSO BEING THE WEST CORNER OF LOT 3 (LOT 3), BLOCK 17, OF THE SAID MEMORIAL FOREST SUB.;

THENCE ALONG THE COMMON LINE OF THIS TRACT AND THE SAID LOT 3, SOUTH 15°54'25" EAST, A DISTANCE OF 130.55 FEET TO A PK NAIL IN CONCRETE FOUND FOR THE EAST CORNER OF THIS TRACT, ALSO BEING THE EAST CORNER OF THE SAID LOT 2, ALSO BEING THE SOUTH CORNER OF THE SAID LOT 3, ALSO BEING A POINT ALONG THE SOUTHWEST BOUNDARY LINE OF THE SAID LOT 1, ALSO BEING A POINT ALONG THE NORTHWEST BOUNDARY LINE OF THE SAID RUSTLING OAKS DRIVE (RUSTLING OAKS DR.), A 50 FOOT RIGHT-OF-WAY;

THENCE ALONG THE COMMON LINE OF THIS TRACT, AND THE SAID RUSTLING OAKS DR., SOUTH 74°27'08" WEST, A DISTANCE OF 91.74 FEET TO A 5/8" IRON ROD WITH AN ORANGE PLASTIC CAP MARKED "CARLOMAGNO RPLS 1562" SET FOR A SOUTHWEST ANGLE POINT OF THIS TRACT, ALSO BEING A POINT ALONG THE SOUTHWEST BOUNDARY LINE OF THE SAID LOT 1, ALSO BEING A POINT ALONG THE NORTHWEST BOUNDARY LINE OF THE SAID RUSTLING OAKS DR., FROM WHICH A 1" IRON ROD FOUND FOR REFERENCE BEARS: NORTH 74°15'04" EAST, A DISTANCE OF 11.59 FEET;

THENCE ALONG THE COMMON LINE OF THIS TRACT AND THE RIGHT-OF-WAY OF THE SAID RUSTLING OAKS DR., SOUTH 74°15'04" WEST, A DISTANCE OF 115.65 FEET TO A 1/2" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "RPLS 2972" FOUND FOR THE SOUTH CORNER OF THIS TRACT, ALSO BEING THE SOUTH CORNER OF THE SAID LOT 1, ALSO BEING A POINT ALONG THE NORTHWEST RIGHT-OF-WAY LINE OF THE SAID RUSTLING OAKS DR., ALSO BEING A POINT ALONG THE EAST RIGHT-OF-WAY LINE OF THE SAID VILLA MARIA RD.;

THENCE ALONG THE COMMON LINE OF THIS TRACT AND THE RIGHT-OF-WAY OF THE SAID VILLA MARIA RD., NORTH 02°15'07" EAST, A DISTANCE OF 136.68 FEET TO THE PLACE OF BEGINNING CONTAINING 0.55 ACRES.

FINAL PLAT

Memorial Forest IV Subdivision, Phase 2 Block 17, Lots 1R & 2R 0.55 Acres

Being a Replat of Block 17 Lots 1 & 2
Memorial Forest IV Phase 2
Volume 365, Page 397
John Austin Survey, A-2
Bryan, Brazos County, Texas
April 2026

Owner:
Bogost Nikolas
2501 Rustling Oaks Dr
Bryan, TX 77802

Owner:
Stephen O. & Abimbola Babalola
2503 Rustling Oaks Dr
Bryan, TX 77802



Surveyor:
Carlomagno Surveying, Inc.
2651 Boonville Rd, Unit 140,
Bryan, Texas 77808
(979)775-2873

PO Box 5192
Bryan, TX 77805
979-739-0567
TBPE F-9951