GOVERNING SPECIFICATIONS

BRYAN/COLLEGE STATION 2012 UNIFIED DESIGN GUIDELINES, MANUALS, TECHNICAL SPECIFICATIONS, & STANDARD CONSTRUCTION DETAILS

CITY OF BRYAN REFERENCE SPECIFICATIONS

ALL APPLICABLE SUBSECTIONS WITHIN:
SECTION I WATER
SECTION II WASTEWATER
SECTION III DRAINAGE
SECTION IV SITE
SECTION V STREETS

SECTION VI ENVIRONMENTAL SECTION VII TRAFFIC


SECTION VIII MISCELLANOUS

# SITE PLANS FOR LIVING HOPE BAPTIST CHURCH (PHASE ONE)

KAZMEIER GARDENS LOT 1R, BLOCK 4 BRYAN, BRAZOS COUNTY, TEXAS JANUARY, 2017

### INDEX OF SHEETS

SHEET	TITLE	#
	CIVIL SITE PLAN COVER PAGE	1
C1.1	OVERALL SITE PLAN	2
C2.1	EROSION CONTROL PLAN	3
C3.1	GRADING PLAN	4
C4.1	SIDEWALK PLAN	5
C6.1	LANDSCAPE PLAN	6
C7.1	NOTES AND DETAILS	7
C7.2	NOTES AND DETAILS	8
C7.3	NOTES AND DETAILS	9



ALFRED A. PAINE

97221

CONSERVATION


ON ALERO


OWNER & DEVELOPED BY: LIVING HOPE BAPTIST CHURCH 2500 S. COLLEGE AVENUE BRYAN, TEXAS 77801

**ENGINEER:** 




DON DURDEN, INC
d.b.a. CIVIL ENGINEERING CONSULTANTS
4101 S. TEXAS AVE, SUITE A
BRYAN, TEXAS 77802
TEL: (979) 846-6212
FAX: (979) 846-8252
REGISTRATION #F-2214





HAY BALE CHECK STRUCTURE

NOT TO SCALE



## VICINITY MAP NOT TO SCALE FINFEATHER LAKE TRAC

#### SITE DESCRIPTION

PROJECT NAME: LIVING HOPE BAPTIST CHURCH MULTI USE CHURCH FACILITY OWNER INFORMATION: LIVING HOPE BAPTIST CHURCH BRYAN

PROJECT LOCATION: APPROXIMATELY 9.28 ACRES WITHIN THE KAZMEIER GARDENS, BLOCKS 4&5 RESERVE TRACTS LOCATED ON THE NORTH SIDE OF BEASON STREET, BRYAN, BRAZOS COUNTY, TEXAS. LATITUDE: N 30°39'04"

LONGITUDE: W 96'22'13"
TOTAL SITE AREA IS: 9.28 ACRES TOTAL AREA OF SITE EXPECTED TO BE DISTURBED IN PHASE 1: 3.86 ACRES EXISTING SITE CONDITIONS:

EXISTING SITE CONDITIONS: LAND USE: VACANT LAND COVER: GRASSED PASTURE, SPARSE TREES/BRUSH AVERAGE GROUND SLOPE: 3% SCS CURVE NUMBER: 80 RATIONAL 'C' FACTOR: 0.35

RECEIVING WATERS: BURTON CREEK TRIBUTARY D.1 BOONVILLE URBAN COMPLEX, 0 TO 3 PERCENT SLOPES (BrB- USDA SOIL SURVEY) SANDOW URBAN COMPLEX, (Sb- USDA SOIL SURVEY) HYDROLOGIC SOIL GROUP: C & D

LAND USE: COMMERCIAL STRUCTURE WITH PARKING, PRIVATE DRIVES & UTILITIES. PRIMARY STANDARD INDUSTRIAL CLASSIFICATION CODE (SIC): 1542 SECONDARY STANDARD INDUSTRIAL CLASSIFICATION CODE (SIC): 1623 SCS CURVE NUMBER: 84 RATIONAL 'C' FACTOR: 0.50

NATURE OF ACTIVITIES: CLEARING OF EXISTING TREES & BRUSH; STRIPPING OF TOPSOIL; SITE CUT/FILL OPERATIONS, CONSTRUCTION OF STRUCTURES, RECREATIONAL FACILITIES, PRIVATE DRIVES, UTILITIES & DETENTION POND.

SEQUENCE OF MAJOR ACTIVITIES: . INSTALL SILT FENCE AT DOWNSTREAM LIMITS OF CONSTRUCTION AREA. 2. INSTALL ROCK CONSTRUCTION ENTRANCE (33'x50') WITH SEDIMENTATION TRAP.
3. INSTALL HAY BALE CHECK STRUCTURE. INSTALL GRAVEL FILTER BAGS.
 CLEAR SITE.

6. EARTHWORK: SITE CUT/FILL, GRADING, UTILITY INSTALLATION, PAVING OPERATIONS.
7. CONSTRUCTION OF RECREATION FACILITIES AND PAVILION.
8. AFTER ESTABLISHMENT OF GRASS, REMOVE ALL TEMPORARY EROSION CONTROL (SILT-FENCE/CONST. ENTRANCES); HYDROMULCH OR SOD ALL AREAS NOT HAVING PERMANENT GRASS COVERAGE AS DEFINED.

#### **GENERAL NOTES**

1. ALL UTILITIES AND SERVICE LINES SHOWN ARE TAKEN FROM RECORD INFORMATION SUPPLIED BY THE UTILITY OWNER OR HORIZONTALLY LOCATED BY INDEPENDENT LOCATORS. CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONDITIONS PRIOR TO CONSTRUCTION. OWNER AND ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF INFORMATION OR DATA RELIED ON TO DEPICT UNDERGROUND FACILITIES. CONTRACTOR IS TO CONTACT OWNERS OF ALL UTILITIES AND SERVICE LINES WITHIN THE PROJECT AREA AND NOTIFY OF INTENT AT LEAST 1 WEEK PRIOR O CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS. CONTRACTOR IS TO VERIFY THE EXACT LOCATION AND VERTICAL POSITIONING OF ALL PIPELINES, EXISTING UTILITIES, AND SERVICE LINES WITHIN THE PROJECT AREA WHETHER SHOWN ON THE PLANS OR NOT, AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. CONTRACTOR IS TO MAINTAIN STRUCTURAL INTEGRITY OF ALL PIPELINES, ELECTRIC TRANSMISSION POLES AND LINES, PERMANENT AND TEMPORARY UTILITIES. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DONE TO EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CLEARING/DIRTWORK ACTIVITIES.

2. CONTRACTOR TO CONTACT TEXAS 811 AND THE CITY OF BRYAN © (979) 209-5900 48 HOURS PRIOR TO CONSTRUCTION. SPECIFIC ATTENTION SHOULD BE PAID TO FRANCHISE UTILITIES, VERIZON, GTE, ECT. SHOULD A CONFLICT ARISE BETWEEN THE PROPOSED CONSTRUCTION AND AN EXISTING UTILITY, CONTACT CEC 48 HOURS PRIOR TO

3. ALL DISTURBED AREAS NOT TO BE PAVED ARE TO HAVE ESTABLISHMENT OF GRASS AS OUTLINED IN THE DESCRIPTION OF CONTROLS, STABILIZATION PRACTICES NOTES. 4. ALL SWALE AREAS (BOTTOM WIDTHS & SIDE SLOPES) ARE TO BE PREPARED AND HYDROMULCHED FOR PERMANENT ESTABLISHMENT OF VEGETATION. PRIOR TO HYDROMULCHING OPERATIONS. CONTRACTOR TO REPLACE TOPSOIL TO A DEPTH OF 6" TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED. FINAL GRADES WITH ESTABLISHED VEGETATION SHALL BE AS CALLED OUT ON THE GRADING PLAN. 5. CONTRACTOR IS TO MAINTAIN EROSION CONTROL THROUGHOUT DURATION OF THE PROJECT AND UNTIL VEGETATION IS ESTABLISHED. INSURE SEDIMENT IS NOT TRANSPORTED DOWNSTREAM FROM PROJECT VIA HAY BALES, BRUSH PILE AND SILT FENCE INSTALLATIONS. IF EXCESSIVE EROSION IS OBSERVED IN THE FIELD, ADDITIONAL EROSION CONTROLS SHALL

6. CONTRACTOR SHALL NOT ALLOW SEDIMENT TO ENTER THE DOWNSTREAM CHANNEL. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OF THE DOWNSTREAM CHANNEL AREAS AND RESTORING TO ORIGINAL CONDITION, INCLUDING ESTABLISHMENT OF REVEGETATION SHOULD CONSTRUCTION SEDIMENT BE FOUND OUTSIDE THE LIMITS OF CONSTRUCTION. 7. CONSTRUCTION EXITS AND ASSOCIATED SEDIMENT TRAPS ARE TO BE CLEANED REGULARLY, CONTRACTOR TO ENSURE NO MUD IS TRACKED ON TO EXISTING CITY OR STATE ROADWAYS. IF TRACKING OCCURS CONTRACTOR IS TO INSURE THAT MUD IS NOT ALLOWED O REMAIN BEYOND THE END OF EACH WORK DAY.

8. SEDIMENT IS TO BE CLEANED FROM SILT FENCING OR OTHER SEDIMENT CONTROL DEVICES WHEN DEPTH OF SEDIMENT REACHES ~1/2 TOTAL HEIGHT OF DEVICE. CONTRACTOR IS TO INSURE EROSION CONTROL DEVICES ARE CONSISTENTLY INSTALLED AND

9. IN AREAS ADJACENT TO POND AND CHANNEL SIDE SLOPES, PROVIDE A MINIMUM 8" HIGH MOUND OF EARTH MATERIAL AT THE TOP OF ALL SLOPES. MAINTAIN MOUND UNTIL VEGETATION IS COMPLETELY ESTABLISHED ON SIDE SLOPE THEN REMOVE/REGRADE TO A SMOOTH SURFACE CONSISTENT WITH ADJACENT GRADES TO ALLOW FOR POSITIVE DRAINAGE INTO THE POND OR CHANNEL AREAS.

10. PRIOR TO FINAL COMPLETION, STORM SEWER INLET IS TO BE CLEANED OF DEBRIS AND

#### LEGEND: AREA OF CLEARING, SOIL DISTURBANCE SILT FENCE CONSTRUCTION ENTRANCE GRAVEL FILTER BAGS ---- 305 ----**EXISTING CONTOUR**

#### **DESCRIPTION OF CONTROLS**

EROSION AND SEDIMENT CONTROL:
1. SILT FENCE
2. ROCK CONSTRUCTION ENTRANCE
3. HAY BALES
4. GRAVEL FILTER BAGS

INSTALL EROSION & SEDIMENT CONTROL DEVICES PER DETAILS HEREON. SEDIMENT MUST BE REMOVED FROM SEDIMENT CONTROL DEVICES PRIOR TO SEDIMENT REACHING 1/2 THE HEIGHT OF THE DEVICE OR STRUCTURE. IF SEDIMENT ESCAPES FROM THE SITE AREA, ACCUMULATIONS MUST BE REMOVED AT A FREQUENCY TO MINIMIZE FURTHER NEGATIVE EFFECTS, AND WHENEVER FEASIBLE, PRIOR TO THE NEXT RAIN EVENT.

TEMPORARY STABILIZATION: ALL STOCK PILED AND OTHER DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES TEMPORARILY CEASE FOR AT LEAST 21 DAYS WILL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN THAT AREA.

PERMANENT STABILIZATION: ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASE SHALL BE SODDED OR HYDROMULCH SEEDED (AS PER PLAN) FOR PERMANENT EROSION CONTROL NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN ACCORDANCE WITH TXDOT 162/164. PRIOR TO FINAL REVEGETATION, CONTRACTOR IS TO REPLACE TOPSOIL TO A DEPTH OF 8". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND

HYDROMULCH: TO BE "EXCEL FIBERMULCH II W/ TACKIFIER - APPLICATION RATE OF 2500 LBS/ACRE. GRASS SEED AND FERTILIZER TO BE INCORPORATED INTO GRASS SEED MIX: SUMMER-HULLED COMMON BERMUDA GRASS, MIN. 85% PURE WINTER-UNHULLED COMMON BERMUDA GRASS, MIN. 85% PURE LIVE SEED @ 90 lbs. PER ACRE + ANNUAL RYE GRASS, MIN. 85% PURE LIVE SEED @ 175 lbs. FERTILIZER: 3-1-2 RATIO FERTILIZER W/ SULFUR & TRACE ELEMENTS @ 350

MAINTENANCE: SHALL CONSIST OF WEEDING, FERTILIZING, INSECT CONTROL, WATERING, REPLANTING, MOVING, MAINTAINING OF EXISTING GRADES, AND REPAIR OF ANY EROSION DAMAGES FOR ALL AREAS WHERE SEEDING AND MULCHING WORK IS COMPLETED. MAINTENANCE TO BE CONDUCTED DURING THE PLANTING PERIOD THRU 90 DAYS AFTER THE WORK IS COMPLETED, INSPECTED AND ADDROVED BY THE ENCINEED AND OWNER.

GUARANTEE: CONTRACTOR IS RESPONSIBLE FOR WATERING, MAINTENANCE AND GUARANTEE: CONTRACTOR IS RESPONSIBLE FOR WATERING, MAINTENANCE AND ESTABLISHMENT OF GRASS FOR A PERIOD OF 90 DAYS AFTER FINAL REVEGETATION APPLICATION FOR PERMANENT EROSION CONTROL. CONTRACTOR IS TO GUARANTEE ALL PLANTED MATERIAL GROWTH AND COVERAGE FOR A PERIOD OF 6 MONTHS. GROWTH AND COVERAGE SHALL BE DEFINED AS 95% OF THE PLANTED AREA WITH UNIFORM COVERAGE OF GRASS GREATER THAN 1" IN HEIGHT WITH NO BARE SPOTS GREATER THAN 2 SQUARE FEET.

-PROVIDE A SECOND APPLICATION OF SPECIFIED SOD OR HYDROMULCH SEEDING (AS PER PLAN) TO BARE AREAS NOT MEETING SPECIFIED COVERAGE - TO BE PERFORMED WITHIN 60 DAYS OF INITIAL APPLICATION AND IMMEDIATELY UPON NOTIFICATION BY THE ENGINEER TO REPLANT.

RECORD KEEPING: CONTRACTOR IS RESPONSIBLE FOR RECORDING & MAINTAINING THE FOLLOWING:

1. DATES WHEN MAJOR GRADING ACTIVITIES OCCUR

2. DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE. 3. DATES WHEN STABILIZATION MEASURES ARE INITIATED.

RECORDS MUST BE KEPT WITH THE SWP3 AND MADE READILY AVAILABLE UPON REQUEST TO THE PARTIES IN PART III.D.1 OF THE TPDES GENERAL PERMIT STRUCTURAL CONTROL PRACTICES:
TEMPORARY EROSION CONTROLS TO INCLUDE INSTALLATION OF SILT FENCE,

GRAVEL FILTER BAGS AND CONSTRUCTION ENTRANCE(S). CONTRACTOR SHALL PREVENT TRANSPORT OF SEDIMENT TO DOWNSTREAM AREAS AND IS RESPONSIBLE FOR CLEANUP AND RESTORATION IF SUCH SHOULD OCCUR.

SILT FENCE TO BE INSTALLED PER DETAIL AT TOE OF DOWNHILL SLOPES AS SHOWN ON PLAN. HAY BALE CHECK STRUCTURES (IF NEEDED) ARE TO BE INSTALLED PER PLAN AT UPSTREAM END OF OUTLET WORKS. ALL EROSION CONTROL DEVICES ARE TO BE MAINTAINED UNTIL ESTABLISHMENT OF GRASS OCCURS.

PERMANENT STORM WATER CONTROLS: STORM WATER WILL DRAIN TO THE PROJECT SPECIFIC DETENTION POND AND DRAINAGE FACILITY. STORM WATER DETENTION WILL BE PROVIDED ON—SITE AS SHOWN HEREON.

CONTRACTOR IS TO INSURE NO CONSTRUCTION DEBRIS OR MUD IS TRACKED OR DISCARDED ONTO ANY PUBLIC OR PRIVATE STREETS OR LANDS AND IS RESPONSIBLE FOR CLEANUP AFTER EACH DAYS WORK. INSTALL ROCK CONSTRUCTION ENTRANCE AS INDICATED WITH CURB PROTECTION. CONTRACTOR IS RESPONSIBLE TO RESTORE ANY DAMAGE DONE TO EXISTING STREETS OR INFRASTRUCTURE

WASTE MATERIALS:
ALL WASTE MATERIALS ARE TO BECOME PROPERTY OF THE CONTRACTOR AND ARE TO BE REMOVED AND DISPOSED OF OFF-SITE. NO ON-SITE BURYING OF WASTE MATERIALS IS ALLOWED. AT THE END OF EACH WORKING DAY, THE CONTRACTOR SHALL GATHER AND COLLECT ALL RUBBISH AND DEBRIS AND STORE IN AN ACCEPTABLE MANNER WHICH PREVENTS MATERIALS FROM BEING BLOWN OR OTHERWISE REDISTRIBUTED ACROSS THE SITE OR ADJACENT LANDS OR WATER COURSES.

HAZARDOUS WASTE: ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF AS PER LOCAL OR STATE REGULATIONS AND IN ACCORDANCE WITH MFR'S SPECIFICATIONS.

TIMING OF CONTROLS/MEASURES

➤ INSTALL SILT FENCING. → INSTALL HAY BALE CHECK STRUCTURES > INSTALL ROCK CONSTRUCTION ENTRANCE(S)
> DISTURBED AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY
CEASES FOR MORE THAN 21 DAYS ARE TO BE STABILIZED WITH HYDROMULCH SEEDING OR BROADCAST SEEDING (AS PER PLAN) NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY IN THAT

AREA.

DURING CLEARING/GRADING ACTIVITIES, SEDIMENT COLLECTING AT CHECK STRUCTURES AND SILT FENCE SHALL BE REMOVED AS IT REACHES 1/2 THE HEIGHT OF THE STRUCTURE.

ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASE SHALL BE HYDROMULCH SEEDED OR BROADCAST

LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY. IN THE EVENT OF FLOODING OR OTHER UNCONTROLLABLE SITUATIONS
WHICH PROHIBIT ACCESS TO THE INSPECTION SITES, INSPECTIONS MUST BE CONDUCTED AS SOON AS ACCESS IS PRACTICABLE.

CONTRACTOR PERSONNEL FAMILIAR WITH THE SWP3 MUST INSPECT DISTURBED AREAS THAT HAVE NOT BEEN FINALLY STABILIZED, AREAS USED FOR STORAGE OF MATERIALS EXPOSED TO PRECIPITATION, AND STRUCTURAL CONTROLS FOR EVIDENCE OF OR POTENTIAL FOR POLLLITANTS ENTERING THE DRAINAGE SYSTEM. SEDIMENT & EROSION CONTROL DEVICES MUST BE INSPECTED TO ENSURE PROPER OPERATION, VEHICLE ENTRANCE/EXIT LOCATIONS MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT INSPECTIONS MUST BE CONDUCTED AT LEAST ONCE EVERY SEVEN (7)

CALENDER DAYS OR ONCE EVERY FOURTEEN (14) CALENDER DAYS AND WITHIN TWENTY FOUR (24) HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. THE SWP3 MUST BE MODIFIED BASED ON RESULTS OF INSPECTIONS, AS NECESSARY, TO BETTER CONTROL POLLUTANTS IN RUNOFF. REVISIONS TO THE SWP3 TO BE COMPLETED WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE INSPECTION IN ACCORDANCE WITH THE TPDES GENERAL A REPORT IN ACCORDANCE WITH THE TPDES GENERAL PERMIT MUST BE MAINTAINED BY THE CONTRACTOR AND RETAINED AS PART OF THE SWP3.

------INLET BOX BAG IS TO HAVE A TIGHT CURB CONTACT WITH NO GAPS PLACE GRAVEL FILTER BAGS SUCH THAT NO GAPS ARE EVIDENT.

1. GRAVEL FOR FILTER BAGS TO BE 3/4" GRAVEL.

2. FILTER BAGS TO BE PERVIOUS BURLAP BAGS OR SYNTHETIC NET BAGS (1/8" MESH) APPROX. 24" LONG, 12" WIDE AND 6" HIGH.

3. MAINTAIN FROM INSTALLATION OF INLET/DRIVEWAY THROUGH EACH STAGE OF ROADBED CONSTRUCTION (SUBGRADE, BASE, HMAC) UNTIL SUBSTANTIAL COMPLETION OF PROJECT.

4. CLEAN SEDIMENT ACCUMULATION AS REQUIRED ALLOWING NO MORE THAN 3" OF SEDIMENT BUILD-UP AROUND BAGS.

GRAVEL FILTER BAG

NOT TO SCALE


INIL ENGINEERIR S. TEXAS A BRYAN, TEXA TEL: (979) 8 FAX: (979) 8


0 6,0


SHEET NO.


TXDOT TYPE 1-CONSTRUCTION ENTRANCE/EXIT

NOT TO SCALE












**PLANT LIST:** COMMON NAME (BOTANICAL NAME) **CANOPY TREES:** 3" CALIPER MINIMUM AT 12" ABOVE GRADE. (Quercus virginiana) MATURE CROWN HEIGHT GREATER THAN **NON-CANOPY TREES:** 1.5" CALIPER, MINIMUM (Lagerstroemia indica) AT 12" ABOVE GRADE. "Watermelon Red" MAX HEIGHT LESS THAN SHRUBS USED FOR SCREENING MUST BE 4' TALL WHEN PLANTED COMMON BERMUDA GRASS 10/100 SI (Cynodon dactylon) \*997 SF = 15% MAX ALLOWANCE OF TOTAL LANDSCAPING POINTS FOR GROUNDCOVER SITE LANDSCAPE CALCULATIONS LANDSCAPING REQUIREMENTS: POINT CALCULATIONS: TOTAL DEVELOPED AREA: 1.02 ACRES = 44293 SF REQUIRED LANDSCAPING: 15% OF DEVELOPED AREA 44293 X 15% = 6644 SF 6644 = SF\_\_\_\_\_\_\_ POINTS REQUIRED: 6644 SF PROVIDED LANDSCAPING: NEW CANOPY TREES (Container) 10 @ 350 SF (3" CAL. minimum) 3500 = SFNEW NON-CANOPY TREES (Container) 14 @ 150 SF (1.5" CAL. minimum) 2100 = SF30 @ 10 SF (2 gal. minimum) 300 = SFGRASSES & GROUNDCOVER 997 = SF-----TOTAL POINTS PROVIDED: **END ISLAND CALCULATIONS** (-) END ISLAND REQUIRED: 10 X 180 SF EXCESS ISLAND AREA: SCALE: 1"=30 448 180





CIVIL ENGINEERII
CIVIL ENGINEERII
S. TEXAS A
BRYAN, TEXA
TEL: (979) 8
FAX: (979) 8
REGISTRATIO








5" - 7" THICKNESS




























NOT TO SCALE















C7.1


SHEET NO.












**OR ANGLE TAP - 1-1/2"** 


B/CS UNIFIED STANDARD DETAIL


CITY OF BRYAN
The Good Life, Texas Style."


**JULY 2016** 

W6-02










SHEET NO.



NOT TO SCALE

K:\data\BCS\Proj\_2016\E0554600\_LIVING HOPE BRYAN — 9.29AC\cadd\Engineering\E0554600—C7.1—Notes and Details.dwg — January 6, 2


NOT TO SCALE


DRAWN BY: LC
APPROVED: AA

JOB NO: E055460

ONDURDEN, IN a.CIVIL ENGINEERING CONSULTAI 101 S. TEXAS AVE, SUITE BRYAN, TEXAS 77802 TEL: (979) 846-6212 FAX: (979) 846-8252 REGISTRATION #F-2214







NG HOPE BAPTIST CHURCH
PHASE 1
NOTES AND DETAILS
AN, BRAZOS COUNTY, TEXAS

ET NO.

C7.3