



SCHULTZ
Engineering, LLC
911 Southwest Pkwy E.
College Station, Texas 77840
979.764.3900
TBPE FIRM NO. 12327

DESIGNED

SURVEYED

DATE

DRAWN

APPROVED

JOB NO.

DATE

APRIL 2025

LECEND

LEGEND
PROPERTY BOUNDARY
ADJACENT PROPERTY BOUNDARY
RIGHT OF WAY
LOT LINE
EXISTING PUBLIC UTILITY EASEMENT
EXISTING PUBLIC ACCESS EASEMENT
EXISTING PRIVATE ACCESS EASEMENT
— — — — — — EXISTING PUBLIC DRAINAGE EASEMENT
·EXISTING PRIVATE DRAINAGE EASEMENT
EXISTING CURB AND GUTTER
·EXISTING STORM PIPE
W-8EXISTING WATERLINE, SIZE NOTED
S-8EXISTING SANITARY SEWER LINE, SIZE N
——————————————————————————————————————
———— UE ————FXISTING UNDERGROUND FLECTRIC LINE

———AE———EXISTING OVERHEAD ELECTRIC LINE

- 1. DEMOLITION OF EXISTING STRUCTURES AND IMPROVEMENTS SHALL INCLUDE ALL WORK CONTAINED ON THESE PLANS, BUT SHALL NOT BE LIMITED TO THE ITEMS SPECIALLY IDENTIFIED. ANY MATERIALS TO BE DEMOLISHED OR CLEARED SHALL BE COMPLETELY REMOVED AND DISPOSED OF. THIS WORK WILL NOT ONLY CONSIST OF ABOVE GROUND ITEMS, BUT UNDERGROUND ELEMENTS AS WELL, INCLUDING BUT NOT LIMITED TO: TREE ROOTS, FOUNDATION SYSTEMS, OLD PIPES, ETC. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY ADDITIONAL ITEMS THAT REQUIRE DEMOLITION, NOT IDENTIFIED ON THESE PLANS, PRIOR TO REMOVAL.
- 2. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO STAGE AND SEQUENCE ALL DEMOLITION WORK WITH UTILITY COMPANIES TO PROVIDE MINIMAL INTERRUPTION AND INCONVENIENCE OF UTILITY SERVICES.
- 3. DEMOLISHED SURPLUS MATERIAL SHALL BE LEGALLY DISPOSED OF OFF-SITE. 4. ALL PAVEMENT EDGES, BOUNDING THE CONSTRUCTION AREA & MATCHING WITH NEW CONSTRUCTION, SHALL BE NEATLY SAW CUT, UNLESS GRAVEL. FLEXIBLE PAVEMENT SHALL BE SAW CUT A MINIMUM OF 24" BEYOND ANY PROPOSED STRUCTURES.
- 5. THE CONTRACTOR SHALL CLEAR ALL RIGHT-OF-WAYS AND EASEMENTS CONTAINED IN THESE CONSTRUCTION DRAWINGS.
- 6. THE CONTRACTOR SHALL FIELD VERIFY AND LOCATE ALL EXISTING UTILITIES ON SITE PRIOR TO DEMOLITION.
- 7. THE CONTRACTOR SHALL PERFORM DEMOLITION ACTIVITIES AS NOTED AND SHOWN ON THESE PLANS AND AS DIRECTED BY THE OWNER/ DEVELOPER. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN ANY PERMITS AND PAY ANY FEES REQUIRED FOR DEMOLITION AND DISPOSAL FROM THE APPROPRIATE AUTHORITIES.
- 8. THE CONTRACTOR SHALL INSTALL ALL EROSION AND SEDIMENT CONTROL DEVICES, AS SHOWN, ON THE EROSION CONTROL PLAN PRIOR TO COMMENCING DEMOLITION WORK.
- 9. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES THAT ARE TO REMAIN IN PLACE.
- 10. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO AVOID UNNECESSARY DAMAGE TO ANY EXISTING ROAD SURFACE.
- 11. ALL EXISTING ITEMS THAT ARE TO REMAIN IN PLACE WHICH ARE DAMAGED DURING CONSTRUCTION SHALL BE RESTORED TO ORIGINAL CONDITION, OR BETTER, AT THE SOLE EXPENSE OF THE CONTRACTOR.
- 12. SHOULD ANY EXISTING UTILITIES NOT SHOWN OR SHOWN INCORRECTLY ON THIS PLAN BE FOUND ON SITE, THE CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER IMMEDIATELY TO DISCUSS ANY POSSIBLE CONFLICTS BEFORE PROCEEDING WITH ANY WORK IN THAT AREA.
- 13. ALL CONSTRUCTION ACTIVITIES, INCLUDE CLEARING, GRUBBING, AND GRADING SHALL BE WITHIN THE LIMITS OF DISTURBED AREA SHOWN ON THIS PLAN.

FILE NAME: 24-211

PURPOSES.